

Stannah

MIDLIFT SL+

ELECTRICAL WIRING MANUAL

ISSUE:

15


**THIS MANUAL IS TO
BE LEFT WITH THE
FOLLOWING
CONTRACT:**

**STANNAH PART NO:
916143**



Stannah

INDEX

UPDATED DRAWINGS (*)	DRAWING NUMBER	REV	DRAWING DESCRIPTION	PAGE NUMBER
	9448-055	C	Midilift SL + main key wiring diagram	1
	9448-059	A	Midilift SL + carriage component tray connection details	2
	9448-003	A	Midilift XL + controller carriage cover connection details	3
	9448-061	A	Midilift SL + trailer cable connection details	4
	9448-056	A	Midilift SL + Trailer connection box relay connection details	5
	9448-062	D	Hydrax Pump motor with L10 valve connection details.	6
	9448-006	C	Midilift XL + landing station with call isolation connection details	7
	9448-007	C	Midilift XL + landing station connection details	8
	9448-008	A	Midilift XL + landing door lock and beak connection details	9
	9448-009	A	Midilift XL + landing station loom connection details	10
*	9446-60		Midilift second entrance at one level connection details	11
	9448-057	A	Midilift reset and encoder switch connection details	12
	9448-011	C	Midilift XL + landing autodoor connection details	13
	9448-012	C	Midilift XL + carriage DDU connection details	14
	9448-013	A	Midilift XL + solenoid feed plunger	15
	9448-014	E	Midilift XL + autodial connection details	16
	9448-015	C	Midilift XL + telephone connection details	17
	9446-009	B	Midilift SL Multi-floor controller pit stop/prop connection details	18
	9448-020	B	Midilift XL + car entrance safety edge connection details	19
	9448-058	B	Midilift Carriage roof wiring details - Elite 633 light rays	20
*	9448-058	E	Midilift Carriage roof wiring details - E32 36 light rays	21
	9448-087		Midilift ultimate limit switch connection details	22
	9448-032	A	Midilift XL + alarm sounder connection details	23
	9448-023	A	Midilift XL + external serial control pcb	24
	9448-060	A	Midilift SL + landing control terminals	25
	9448-063	A	Midilift carriage control tray terminal for cabin and power supply	26
	9448-051	A	Midilift landing station isolation by other connection details	27
	9448-054		Midilift XL + Volt free option enclosure connection details	28
	9448-070	B	Midilift Cabin Videx Intercom Connection Details	29
	9448-029	D	Midilift XL+ overload device connection details	30
	9448-088		Pendant control connection details (Midilift multi-floor PCB)	31
	9446-55		Multi-floor - Label Neptis door operator connection details	32
	9452-044	A	Midilift MEMCO GSM (DCP unit) wiring/setup guide	33
	APPENDIX A	A	Midilift SL + installation guide	34
	APPENDIX B	E	Midilift SL + fault code list	35
	APPENDIX C	B	Midilift SL + learn mode procedure	36
	APPENDIX D		Midilift Trailer PCB layout (9300/88)	37
	APPENDIX E		Midilift ESCU PCB layout (9300/91)	38
	APPENDIX F	A	Midilift Control PCB layout (9300/61)	39
	APPENDIX G		Midilift SL + Earth bonding guide	40
	APPENDIX H	C	Midilift SL + load weighing device setup 1 of 2	41
	APPENDIX H	B	Midilift SL + load weighing device setup 2 of 2	42
	APPENDIX I		Midilift SL + Motor calibration procedure	43
	APPENDIX J		Midilift SL + label neptic door operator quick setup guide	44




IMPORTANT NOTE:
 LATCH LANDING OPERATION AND FIRE ALARM SHUTDOWN MUST BE DISABLED DURING INSTALLATION, SERVICE INSPECTION AND WHENEVER CARRIAGE COVER IS REMOVED. REFER TO APPENDIX C FOR PROCEDURE.



NAME: J.NICHOLLS	DATE: 15/01/2013
CHECKED: M.HOOD	DATE: 15/01/2013
MIDLIFT SL + MULTI-FLOOR CONTROLLER MAIN KEY DIAGRAM	
Stannah	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-055	REV: C

REV C: DRAWING UPDATED TO REFLECT UP-ISSUED PCB. JN 03/11/14 ECN A5513.
 REV B: FIRE ALARM INPUT ADDED AND IMPORTANT NOTE. JN 27/05/14 ECN A5573.
 REV A: CONTACTS '7' AND '11' ON RELAYS SR AND DR ARE NOW IN PARALLEL INSTEAD OF SERIES. JN 19/06/13



NAME: J.NICHOLLS DATE: 08/01/2013
 CHECKED: M.HOOD DATE: 08/01/2013

MIDLIFT MULTI-FLOOR BOARD
 CARRIAGE CONTROL TRAY WITH POWER SUPPLY
 CONNECTION DETAILS


Stannah

HEAD OFFICE:
 Anton Mill
 Andover Hampshire
 SP10 2NX England

Tel: 01264 339090 Fax: 337942

DRAWING NO: 9448-059


REV: A



REV D: MOV'S ADDED DUE TO LACK OF NOISE SUPPRESSION ON DC VALVES. 31/10/2017 JN A6108.
 REV C: OVERLOAD RATE UPDATED TO INCLUDE PICCOLO & DIODES REMOVED. 25/11/2014 JN
 REV B: CABLE LOCATION CHANGED TO WIRING INTO TERMINALS INSTEAD OF BOARD. ECN A5505. 27/06/2013 JN
 REV A: WIRE 6 USED FOR L10, CHANGED TO WIRE 9 AND DIODE POSITION CHANGED. ECN A5395. 18/04/2013 JN


NAME: J.NICHOLLS	DATE: 09/10/12
CHECKED: M.HOOD	DATE: 09/10/12
HYDRAX PUMP MOTOR WITH L10 VALVE (PICCOLO DIRECT AND SL+)	
	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England	
Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-062	REV: D

LANDING STATION CONTROL



NAME: J.NICHOLLS	DATE: 17/02/10
CHECKED: M.HOOD	DATE: 17/02/10
MIDLIFT XL+ LANDING STATION CONNECTION DETAILS	
Stannah	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-007	REV: C

REV C: CABLE CHANGED ON 3 CORE + SCREEN. JN 09/06/15 ECN A5667
 REV B: BIT SWITCH ARRANGEMENT ADDED. 27/05/14 JN. A5573
 REV A: REFERENCE TO PLUG WIRING ON DIAGRAM 9448/009 ADDED. UPDATED FOR NEW LOGO AND TEXT FONT.
 20/07/2010 JN. A4659




SEE DIAGRAM 9448/009 FOR CONNECTION DETAILS

WIRE 6
WIRE 7
WIRE 8
WIRE 9
WIRE 10
WIRE 11


6 WAY FEMALE CONNECTOR

6 WAY MALE CONNECTOR

NAME: J.NICHOLLS	DATE: 17/02/10
CHECKED: M.HOOD	DATE: 17/02/10
MIDLIFT XL+ LANDING DOOR LOCK AND BEAK CONNECTIONS DETAILS	
	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-008	REV: A



NAME: J.NICHOLLS	DATE: 17/02/10
CHECKED: M.HOOD	DATE: 17/02/10
MIDLIFT XL+ LANDING STATION LOOM CONNECTION DETAILS	
	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-009	REV: A







IMPORTANT NOTE:
PREWIRED LINKS MUST BE REMOVED PRIOR TO CONNECTING SECOND ENTRANCE AT SAME FLOOR.


Table 1

Number of Floors	Max number of floors with two entrances allowed	Solenoid / brake wiring (wires 1,2,6,7,8,9&11)	Landing call & call accept wiring (wires 3,4,5&10)
5 (XL + 8 SL + only)	1	PL18 - Landing 6	Connected to corresponding landing plug (i.e. double connection). Second entrance: Floor 1 = PL25 Floor 2 = PL23 Floor 3 = PL20 Floor 4 = PL19 Floor 5 = PL17
4	2	PL18 - Landing 6 PL17 - Landing 5	
3	3	PL18 - Landing 6 PL17 - Landing 5 PL19 - Landing 4	
2	2	PL18 - Landing 6 PL17 - Landing 5	



NAME: J.NICHOLLS	DATE: 14/07/20
CHECKED: M.HOOD	DATE: 14/07/20
MIDLIFT MULTI-FLOOR CONTROLLER SECOND ENTRANCE AT ONE LEVEL CONNECTION DETAILS	
<div style="display: inline-block; vertical-align: middle; margin-left: 20px;"> <p>HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England</p> <p>Tel: 01264 339090 Fax: 337942</p> </div>	
DRAWING NO: 9446/60	REV:




NAME: J.NICHOLLS	DATE: 16/08/12
CHECKED: M.HOOD	DATE: 16/08/12
RESET SWITCH AND ENCODER CONNECTION DETAILS	
Stannah	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England	
Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-057	REV: A



CARRIAGE DIGITAL DISPLAY UNIT



IMPORTANT NOTE:
SCREENED WIRE TO BE INSULATED USING HEATSHRINK





NAME: J.NICHOLLS	DATE: 22/10/09
CHECKED: M.HOOD	DATE: 22/10/09

**MIDLIFT XL+
CARRIAGE DDU
CONNECTION DETAILS**

	<p>HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England</p> <p>Tel: 01264 339090 Fax: 337942</p>
--	--------------------------------------------------------------------------------------------------------------------

DRAWING NO: 9448-012	REV: C
----------------------	--------




NAME: J.NICHOLLS	DATE: 17/02/10
CHECKED: M.HOOD	DATE: 17/02/10
MIDLIFT XL+ SOLENOID FEED PLUNGER	
Stannah	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-013	REV: A

IMPORTANT NOTE:

PLEASE ENSURE MENU 26 IN QUICK SET UP IS SET AS FOLLOWED:

- WITHOUT GSM - SET TO 8
- WITH GSM - SET TO 24



NAME: J.NICHOLLS	DATE: 17/02/10
CHECKED: M.HOOD	DATE: 17/02/10

**MIDLIFT CONNECTION DETAILS
AUTODIAL CONNECTION DETAILS**

Stannah


HEAD OFFICE:
Anton Mill
Andover Hampshire
SP10 2NX England

Tel: 01264 339090 Fax: 337942

DRAWING NO: 9448-014

REV: E

REV E: PROGRAMMING DETAILS ADDED. JN 24/10/16 A5823
 REV D: TRAILER NUMBER UPDATED TO SHOW SL+. 27/05/2014 JN A5573.
 REV C: INDUCTIVE LOOP PICTURE ADDED. 30/07/2012 JK A5299.
 REV B: WIRING COLOUR CORRECTED ON THE INDUCTIVE LOOP. 11/07/2011 JN A5007.
 REV A: WIRING CORRECTED TO LINK 0VDC TO GND & UPDATED FOR NEW LOGO AND TEXT FONT. 29/07/2010 JN.



NAME: J.NICHOLLS	DATE: 17/02/10
CHECKED: M.HOOD	DATE: 17/02/10

MIDLIFT XL+
TELEPHONE CONNECTIONS DETAILS

Stannah


HEAD OFFICE:
Anton Mill
Andover Hampshire
SP10 2NX England

Tel: 01264 339090 Fax: 337942



DRAWING NO: 9448-015

REV: C

REV C: TRAILER NUMBER UPDATED TO SHOW SL+. 27/05/2014 JN A5573.
 REV B: ORDER OF BT EXTENSION SOCKET CABLE WIRES CHANGED TO REFLECT MEMCOM INSTALLATION MANUAL DRAWINGS. 05/11/12 JK. A5364
 REV A: UPDATED FOR NEW LOGO AND TEXT FONT. 29/07/2010 JN.




NAME: M.HOOD	DATE: 01/10/07
CHECKED: R.BAUGH	DATE: 01/11/07
MIDLIFT SL MULTI-FLOOR CONTROLLER PIT STOP / PROP CONNECTION DETAILS	
	
<small>HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England</small>	
<small>Tel: 01264 339090 Fax: 337942</small>	
DRAWING NO: 9446-009	REV: B



NAME: M.HOOD	DATE: 17/02/10
CHECKED: J.NICHOLLS	DATE: 17/02/10
MIDLIFT XL+ CAR ENTRANCE SAFETY EDGE CONNECTION DETAILS	
	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-020	REV: B


REV B: G8 CHANGED TO G7C. 04/01/11 JK. A4866
 REV A: UPDATED FOR NEW LOGO AND TEXT FONT. 29/07/2010 JN.





REV B: RX AND TX ALTERED TO SHOW CORRECT INPUT/OUTPUTS. JN. 27/05/14. A5573.
 REV A: G1 AND GND SWAPPED TO AVOID THE POSSIBILITY OF A LINK BETWEEN G1 AND G8. JK. 14/08/13. A5511.

NAME: J.NICHOLLS	DATE: 10/01/13
CHECKED: M.HOOD	DATE: 10/01/13
MIDLIFT	
CARRIAGE ROOF WITH ELITE 633 LIGHT CURTAINS	
WIRING DETAILS	
Stannah	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England	
Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-058	REV: B






IMPORTANT NOTE
ENSURE GREEN CABLE IS TIED BACK & INSULATED



SEE IMPORTANT NOTE



SEE IMPORTANT NOTE



NAME: J.NICHOLLS DATE: 10/01/13
CHECKED: M.HOOD DATE: 10/01/13


**MIDLIFT
CARRIAGE ROOF WITH E32 36 LIGHT CURTAINS
WIRING DETAILS**

HEAD OFFICE:
Anton Mill
Andover Hampshire
SP10 2NX England
Tel: 01264 339090 Fax: 337942


DRAWING NO: 9448-058 REV: E

REV E: LIGHT RAYS UNDATED TO E32-36 TO INCLUDED HARDWIRED LINK. JN. 19/03/21. A6602.
REV D: G1 AND DRM WIRING DETAILS CHANGED ON THE RX LIGHT RAY. JN. 04/08/15. A5688.
REV C: DRAWING UPDATED TO REFLECT NEW MEMCO LIGHT CURTAIN. JN. 03/11/14. A5513.
REV B: RX AND TX ALTERED TO SHOW CORRECT INPUT/OUTPUTS. JN. 27/05/14. A5573.
REV A: G1 AND GND SWAPPED TO AVOID THE POSSIBILITY OF A LINK BETWEEN G1 AND G8. JK. 14/08/13. A5511.

**ULTIMATE
LIMIT SWITCH**



NAME:	M.HOOD	DATE:	24/11/15
CHECKED:	J.NICHOLLS	DATE:	25/11/15
MIDILIFT CABIN ULTIMATE LIMIT SWITCH CONNECTION DETAILS			
		HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-87			REV:



IMPORTANT NOTES:


- 1. ALARM TO BE MOUNTED WITHIN A 5 METRE RADIUS OF THE LIFT.
- 2. SET BIT SWITCHES AS SHOWN.

NAME: J.NICHOLLS	DATE: 17/02/10
CHECKED: M.HOOD	DATE: 17/02/10

**MIDLIFT XL+
ALARM SOUNDER
CONNECTION DETAILS**

Stannah	HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942
----------------	------------------------------------------------------------------------------------------------------

DRAWING NO: 9448-032	REV: A
----------------------	--------




EXTERNAL SERIAL CONTROL PCB TERMINALS (9300/91)


TRAILER PCB TERMINALS (9300/88)

NAME: J.NICHOLLS	DATE: 17/02/10
CHECKED: M.HOOD	DATE: 17/02/10
MIDLIFT XL+ EXTERNAL SERIAL CONTROL PCB	
	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-023	REV: A

SECURITY SYSTEM BY OTHERS



NORALSY KEYPAD OPTION



NAME:	J.NICHOLLS	DATE:	05/01/12
CHECKED:	M.HOOD	DATE:	05/01/12

MIDLIFT XL+
LANDING STATION WITH NORALSY KEYPAD
CONNECTION DETAILS

Stannah


HEAD OFFICE:
Anton Mill
Andover Hampshire
SP10 2NX England

Tel: 01264 339090 Fax: 337942


DRAWING NO: 9448-051

REV: A

FIRE ALARM





VOLT FREE ALARM






NAME: J.KENT	DATE: 30/07/12
CHECKED: M.HOOD	DATE: 30/07/12
MIDLIFT XL+ VOLT FREE OPTION ENCLOSURE CONNECTION DETAILS	
	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-054	REV:

STANDARD HANDSET




SIMPLEX OPTION



NAME: J.KENT	DATE: 09/04/13
CHECKED: M.HOOD	DATE: 09/04/13
MIDLIFT CABIN VIDEX INTERCOM CONNECTION DETAILS	
Stannah	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-070	REV: B



REV C: TRAILER NUMBER UPDATED TO SHOW SL+ & ART.5112/ART.5118 WIRING UPDATED.
 27/05/2014 JN A5573.
 REV A: TERMINAL BLOCK REMOVED. JK. 02/07/13. A5511.



NAME: M.HOOD	DATE: 17/02/10
CHECKED: J.NICHOLLS	DATE: 17/02/10
OVERLOAD DEVICE CONNECTION DETAILS	
	
HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England Tel: 01264 339090 Fax: 337942	
DRAWING NO: 9448-029	REV: D

REV D: WIRE NUMBERS OF 2 CORE CABLE AMENDED TO SUIT UPDATED OVERLOAD. JN 04/12/17
 REV C: WIRE NUMBERS OF 2 CORE CABLE ADDED. MH 12/04/12 A5277
 REV B: DRAWING CHANGED TO REFLECT NEW LOAD WEIGHING DEVICE. 03/02/2012 JK. A5195
 REV A: UPDATED FOR NEW LOGO AND TEXT FONT. 29/07/2010 JN.

INSTALLERS PENDANT CONTROL



NAME: J.NICHOLLS	DATE: 08/08/16
CHECKED: M.HOOD	DATE: 08/08/16


**PENDANT CONTROL
CONNECTION DETAILS
(MIDLIFT MULTI-FLOOR PCB)**

Stannah


HEAD OFFICE:
Anton Mill
Andover Hampshire
SP10 2NX England

Tel: 01264 339090 Fax: 337942


DRAWING NO: 9448-88	REV:
---------------------	------



NOTE:
REFER TO APPENDIX FOR
DOOR OPERATOR QUICK
SETUP GUIDE.



NAME:	J.NICHOLLS	DATE:	30/03/16
CHECKED:	M.HOOD	DATE:	30/03/16
MIDLIFT SL MULTI-FOOR LABEL NEPTIS AUTO DOOR OPERATOR CONNCTION DETAILS			
		HEAD OFFICE: Anton Mill Andover Hampshire SP10 2NX England	
Tel: 01264 339090 Fax: 337942			
DRAWING NO: 9446/55			REV:



MEMCO GSM - Quick setup guide

For full details refer to the 'DPC Installation Guide' which can be accessed on the Avire website (www.avire-global.com)

IMPORTANT NOTE: MAINS SUPPLY SHOULD BE DISCONNECTED BEFORE BEGINNING THIS PROCEDURE.

1. SETTING UP THE DEVICE

- A. Insert SIM card into plug J4, pressing it in until it clicks.
- B. Ensure that the antenna is securely connected to plug J2.
- C. Connect the pre-wired battery lead to plug J3.

2. CHECKING THE NETWORK COVERAGE

- A. Ensure all previous steps have been completed.
- B. Turn the first dip switch SW1 to On.
- C. The five LEDs on the front will show the network signal level.
- D. Once a suitable location has been found, switch SW1 to OFF and fix in position.

3. WIRING THE GSM

- A. Connect the mains power supply to plug J6.
- B. Phone line connection between plug J9 (GSM unit) and CM1/CM2 (lift trailer PCB) as per below:
 - J9 terminal 1 to CM2.
 - J9 terminal 2 to CM1.

4. CONFIGURING THE GSM (via local telephone mode)

- A. Connect an analogue telephone handset into J1A.
- B. Pick up the handset and after hearing the dial tone, enter the access command **##1234##**.
- C. Change parameter value P020 to value 00, by entering the following combination on the handset keypad ***020#00#**.
- D. Hang up the phone to complete configuration.

NAME: J.NICHOLLS	DATE: 02/08/18
CHECKED: M.HOOD	DATE: 02/08/18

MIDLIFT
MEMCO GSM (DCP UNIT)
WIRING / SETUP GUIDE

Stannah

HEAD OFFICE:
Anton Mill
Andover Hampshire
SP10 2NX England

Tel: 01264 339090 Fax: 337942

DRAWING NO: 9452044

REV: A


IMPORTANT NOTE:
IT IS ACCEPTED THAT PERSONS CARRYING OUT THIS INSTALLATION HAVE ALREADY BEEN TRAINED TO THE REQUIRED LEVEL - THIS PROCEDURE IS FOR GUIDANCE ONLY.

CHECK THE FOLLOWING BEFORE BEGINNING PROCEDURE -

- LOWER STRUCTURE IS BUILT AND CARRIAGE IS SECURE WITHIN THE GUIDES.
- LIFT POWER SUPPLY IS TURNED OFF.

STEP 1 - LINK OUT ALL UNINSTALLED LANDING BEAKS AND SOLENOID SAFETY SWITCHES USING LINKING PLUGS PROVIDED.

CONNECT LINKING PLUGS INTO LANDING SOCKETS 1-6 ON THE TRAILER PCB (9300/88).



THESE LINKS ARE REQUIRED TO MAINTAIN A CIRCUIT BETWEEN POINTS 'G4' TO 'G5' AND 'G5' TO 'G6' WITHIN THE SAFETY CHAIN.

STEP 2 - INSTALLATION SHORTING LINK TO BE FITTED BETWEEN TERMINALS G7A AND G8 ON THE CARRIAGE CONTROL TERMINAL RAIL.


THIS LINK IS REQUIRED TO CREATE A TEMPORARY SHORT FOR THE UNINSTALLED ROOF SAFETY AND PLATFORM SWITCHES.

STEP 3 - CONNECT INSTALLERS PENDANT CONTROL BOX.

INSTALLATION OF MIDLIFT SL+ SHOULD NOT BE ATTEMPTED WITHOUT THE USE OF A PENDANT CONTROL BOX.

STEP 4 - SELECT THE INSTALLATION OPERATION FROM THE LEARN MODE INTERFACE ON MAIN CONTROL PCB (9300/61).

WHENEVER USING THE LIFT AS A WORKING PLATFORM LIFT MUST ALWAYS BE OPERATING IN INSTALLATION MODE. ALL LANDING CALLS ARE IGNORED IN THIS MODE.



ALL SWITCHES 'ON' = INSTALLATION MODE OPERATION

STEP 5 - TURN ON LIFT.

STEP 6 - USING THE PENDANT CONTROLLER, RAISE CARRIAGE AND INSTALL CABIN FLOOR AND WORKING PLATFORM.

DRIVE UP = 'RUN' + '2'
DRIVE DOWN = 'RUN' + '1'

STEP 7. INSTALL THE REMAINING STRUCTURE.

ENSURE THAT ALL SAFETY SWITCHES ARE INSTALLED AT THE EARLIEST OPPORTUNITY (I.E. PIT/ROOF AND ULTIMATE LIMIT SWITCHES). REMOVE RELEVANT LANDING STATION LINK PLUGS AS EACH LANDING STATION IS INSTALLED.

STEP 8. TURN OFF LIFT SUPPLY.

STEP 9. REFER TO INSTALLATION MANUAL FOR CONSTRUCTION OF CABIN.

STEP 10. RECORD FLOOR LEVELS.

FOLLOW INSTRUCTION GIVEN IN APPENDIX C WITHIN THE WIRING MANUAL.

IMPORTANT NOTE: IT WILL NOT BE NECESSARY TO HAVE ANY SHORTING PLUGS/LINKS FITTED AT THIS STAGE - ENSURE THAT THEY ARE ALL REMOVED.

**APPENDIX A -
MIDLIFT SL+
INSTALLATION GUIDE**

APPENDIX B – FAULT CODE LIST

Certain fault conditions will cause the controller to latch the lift out of service. When this happens, the relevant fault code will be displayed on all lift digital display units (DDU's) and the lift will be latched out of service.

The lift supply will need to be cycled in order to clear the latch fault and return the lift to normal service (NOTE: After supply has been re-instated the lift will 'RESET' to the bottom floor).

FAULT CODES:

DDU DISPLAY	DESCRIPTION
A	<p>ENCODER MOVEMENT FAULT No encoder movement was detected during last run attempt.</p> <ul style="list-style-type: none"> If lift moved (i.e. is away from floor level) then check encoder assembly for fault. If lift did not move (i.e. is at floor level) then check run circuit for fault.
B	<p>JOURNEY TIME FAULT Maximum journey time exceeded. Check inverter/drive system for errors. Confirm journey time selection using SWITCH 2.</p> <ul style="list-style-type: none"> ON = 30 sec (SL+ / PICCOLO DIRECT) 70 sec (PICCOLO 2:1) OFF = 60 sec (SL+ / PICCOLO DIRECT) 120 sec (PICCOLO 2:1)
C	<p>LIGHT RAY FAULT Lift controller failed to detect a light ray input during the last 10 consecutive door open commands.</p> <ul style="list-style-type: none"> Check for misuse of lift. Possible faulty light ray – monitor 'DRM' input with light ray activated.
D / J	<p>RUN CONTACT FAULT Run contact monitor input received whilst lift is stationary. Check the following –</p> <ul style="list-style-type: none"> Wiring of 'MC' contactor. Faulty 'MC' contactor (i.e. permanently energised).
E	<p>ANTI-SURF FAULT (landing door beaks) Landing door has been manually released whilst lift in normal service. Fault can also occur if door beak contacts have gone out of alignment. Check the following –</p> <ul style="list-style-type: none"> Misuse of lift. Landing door beak alignment.
F	<p>ANTI-CREEP RELAY FAULT Controller has detected an input to terminal 'ACM' (Anti-Creep Monitor) when <u>not</u> in anti-creep mode. Check the following –</p> <ul style="list-style-type: none"> Wiring to Anti-creep Relay. Faulty Anti-Creep Relay (i.e. permanently energised).
G	<p>ANTI-SURF FAULT (car door beaks) Car door has been manually released whilst lift in normal service. Fault can also occur if door beak contacts have gone out of alignment. Check the following –</p> <ul style="list-style-type: none"> Misuse of lift. Car door beak alignment.
I / K	<p>PRE RUN FAULT Fault K - is detected if lift is ready to run (UOK or DOK are ON) but safety chain has been lost at either G4, G5 or G6 <u>without</u> anticreep output set. Fault I - is detected if lift is running in one direction but has 'ready to run' input in opposite direction (i.e. up/down interlock has failed).</p>
R	<p>RESET MODE Lift attempting to reset to bottom floor. If no lift movement or directional arrow shown please check for break in the safety chain.</p>

IMPORTANT NOTE

BEFORE BEGINNING LEARN MODE PROCEDURE -

- CHECK THAT ALL SAFETY DEVICES ARE INSTALLED AND FUNCTIONING CORRECTLY.
- MOTOR CALIBRATION HAS BEEN COMPLETED (APPENDIX I).
- BOTH THE INSTALLER PENDANT CONTROLLER AND DDU/SPEAKER BOX MUST BE USED TO OPERATE THE LIFT IN LEARN MODE DURING INSTALLATION.
- TO ENABLE SERVICE ENGINEERS TO RE-PROGRAMME FLOOR LEVELS, COP PUSH BUTTONS CAN BE USED IN PLACE OF A PENDANT CONTROLLER. SEE 'COP CONTROL' SECTION.

IMPORTANT NOTE:
IT IS ACCEPTED THAT PERSONS CARRYING OUT THIS INSTALLATION HAVE ALREADY RECEIVED FORMAL TRAINING. THIS PROCEDURE IS FOR GUIDANCE ONLY.

SET A MINUS FLOOR
PRESS PENDANT 1
LA WILL APPEAR ON THE DDU

SET BIT SWITCH 1 = MINUS 1 FLOOR
SET BIT SWITCH 2 = MINUS 2 FLOOR
SET BIT SWITCH 3 = GROUND FLOOR

ONCE THE CORRECT BIT SWITCH IS SET, PRESS THE RECORD BUTTON TO RETURN.

SET A FIRE FLOOR
PRESS PENDANT 2
LB WILL APPEAR ON THE DDU

SET BIT SWITCH 1 = 0 FLOOR
SET BIT SWITCH 2 = 1 FLOOR
SET BIT SWITCH 3 = 2 FLOOR
SET BIT SWITCH 1 & 2 = 3 FLOOR
SET BIT SWITCH 1 & 3 = 4 FLOOR

ONCE THE CORRECT BIT SWITCHES ARE SET, PRESS THE RECORD BUTTON TO RETURN.

SET HOMING
PRESS PENDANT 3
LC WILL APPEAR ON THE DDU

CLEAR BIT SWITCH 1 = ENABLED (DEFAULT)
SET BIT SWITCH 1 = DISABLED

LIFT WILL HOME TO LOWEST FLOOR AFTER OF PERIOD OF 15 MINUTES

ONCE THE CORRECT BIT SWITCHES ARE SET, PRESS THE RECORD BUTTON TO RETURN.

SELECT CONSTANT PRESSURE MODE
PRESS PENDANT 1 + PENDANT 2
LD WILL APPEAR ON THE DDU

SET BIT SWITCH 1 = CONSTANT PRESSURE (CONSTANT PRESSURE ON CAR CALLS ONLY)

ONCE THE CORRECT BIT SWITCH IS SET, PRESS THE RECORD BUTTON TO RETURN.

STEP 1
TURN ON SWITCH 4 TO ACTIVATE LEARN MODE (LIFT WILL NOW RESET TO GROUND FLOOR).

STEP 2
LEARN 1 LED WILL APPEAR.

IF A MINUS FLOOR, FIRE SHUTDOWN OR HOMING FLOOR IS REQUIRED PRESS THE CORRESPONDING CAR CALL BUTTON.

SET TYPE OF DOOR

NO BIT SWITCHES = MANUAL DOOR
SET BIT SWITCH 1 = POWER DOOR

ONCE THE CORRECT BIT SWITCH IS SET, PRESS THE 'RECORD' BUTTON.

STEP 3
DRIVE LIFT TO NEXT FLOOR.

STEP 4
ONCE POSITIONED AT FLOOR LEVEL, SET THE APPROPRIATE TYPE OF DOOR

NO BIT SWITCHES = MANUAL DOOR
SET BIT SWITCH 1 = POWER DOOR


STORE THE FLOOR LEVEL BY PRESSING THE 'RECORD' BUTTON.

FLOOR LEVEL IS RECORDED ONCE THE NEXT 'LEARN' LED IS ILLUMINATED.

STEP 5
REPEAT STEPS 3 AND 4 TO PROGRAMME REMAINING FLOORS.

STEP 6
ONCE YOU HAVE PROGRAMMED THE FINAL FLOOR LEVEL, TURN OFF SWITCH 4 TO EXIT LEARN MODE AND RETURN TO NORMAL OPERATION.


PENDANT CONTROLS



COP CONTROLS (FOR SERVICE ENGINEERS)

FLOOR LEVEL 1 - LIFT RUN UP COMMAND REQUIRES CONSTANT PRESSURE.
FLOOR LEVEL 0 - LIFT RUN DOWN COMMAND REQUIRES CONSTANT PRESSURE.

LEARN MODE INTERFACE




LEARN 6
LEARN 5
LEARN 4
LEARN 3
LEARN 2
LEARN 1

RECORD


RUN

- SWITCH 1 - DOOR VOICE ACTIVATION**
ON = ENABLE DOOR OPENING ANNOUNCEMENT
OFF = NO ANNOUNCEMENT
- SWITCH 2 - JOURNEY TIME SELECTION**
ON = 30 SECONDS
OFF = 60 SECONDS
- SWITCH 3 - ADJUSTABLE DOOR DWELL TIME**
ON = 10 SECONDS
OFF = 05 SECONDS
- SWITCH 4 - LEARN MODE ACTIVATION**
WILL PUT LIFT INTO LEARN MODE.

**APPENDIX C
MIDLIFT SL+
LEARN MODE
PROCEDURE**




**APPENDIX D -
TRAILER PCB
LAYOUT**




! WARNING !
 230VAC MAINS
 VOLTAGE
 TERMINALS

**APPENDIX E -
 ESCU PCB
 TERMINATIONS**



**APPENDIX F -
CONTROL PCB
LAYOUT**

**APPENDIX G
MIDLIFT SL+
EARTH BONDING
GUIDE**



Introduction:

Prior to setup, the lift must be run at least 5 times with full rated load and ensure the lift is not tight in the guides. It is also advisable to jump up and down a few times in the lift. Finally, ensure the lift is not resetting on the ground.

CALIBRATION ROUTINE (START HERE).

Important note: If ER.01 appears when the load weighing device is first turned ON, ignore and continue with the below calibration.

1 Enter Setup Mode:

- 1.1 Press and hold the RESET button, then press and hold the ▼ and C buttons and release the reset button, keep ▼ and C pressed until MANU is displayed briefly before showing LEV.

2 Set the Controller with the weight of the empty car:

- 2.1 Press ▼ to move to the TARE function (the TARE value is the car's own weight – set to 0)
- 2.2 Empty lift car
- 2.3 Press E and display will show 0.
- 2.4 Press E again to start 60 second countdown (T-60 to T-0) to allow time for the installer to exit the car (Ensure there is no extra load in the car during this time)
- 2.5 Measurement is complete when MEM□ is briefly displayed and then TARE is shown again

3 Calibration of Load Sensor Controller:

- 3.1 Press ▼ until the HI function is shown (the HI value is used to calibrate the load sensor with a known load)
- 3.2 Press E to select mode
- 3.3 Press ▲ or ▼ buttons to move value to 400kg
- 3.4 Add 400kg of test weight to the cabin. Load must be distributed such that 100kg is placed in each of the 4 corners / quadrants of the cabin.
- 3.5 Press E to start 60 second countdown (T-60 to T-0) to allow time for the installer to exit the car (Ensure there is no extra load in the car during this time).

IMPORTANT NOTE: For Piccolo models only, allow the Fermator cabin and landing doors to close for duration of this 60 second countdown. This will allow the Load Sensor Controller to evaluate maximum load condition.

- 3.6 Measurement is complete when MEM□ is briefly displayed and then HI is shown again.
- 3.7 Remove test weights.

Continued on page 2 of 2...

APPENDIX H
1 OF 2
LOAD WEIGHING
DEVICE SETUP

4 Set Maximum Rated Load:

- 4.1 Press ▼ until the **FSCA** function is shown (the **FSCA** value is the maximum rated load)
- 4.2 Press **E** to select mode
- 4.3 Press ▲ or ▼ buttons to move value to 400kg
- 4.4 Press **E** to confirm, **FSCA** is shown again.

5 Set Overload Alarm:

- 5.1 Press ▼ to activate the **LEV1** mode (the **LEV1** value is a percentage of the maximum rated load that will activate the overload alarm)
- 5.2 Press **E** to select mode
- 5.3 Press ▲ or ▼ buttons to move value to 120%
- 5.4 Press **E** to confirm input. Display will return to **LEV1**.
- 5.5 **LEV2** and **LEV3** are not used.

6 Exit Setup Mode

- 6.1 Press **C** to end calibration and return to normal running. Display will show **SAVE** briefly.

7 Check Readout

- 7.1 Step into car and check the load value has increased by the installers approximate weight.

- 8 Exit the lift car and check display shows 0. If not, the unit can be zeroed by leaning into the empty lift car and pressing '**C**' briefly.

Note: Pressing the **C** button will save the setup at any time. To return to the setup menu follow step 1.1 above and use the ▲ or ▼ buttons to move to the required setting.

Fault Codes

Code	Meaning
ER.01	Negative Load: ER01 indication is displayed alternatively to the measured load (the minus is displayed only up to three numbers, i.e. -999). Check connections and recalibrate.
ER.22	Conversion slope not correct: too high signal from 942 Strain Link (fix 942 to a more rigid part of the lift frame or substitute it). Verify that HI value is entered with the right resolution (use weight at least 80% FSCA).
ER.23	HI value is too low (in engineering units). HI-Tare must be > 10
ER.24	Calibration Load is too low. Increase load.
ER.26	TARE and HI values identical, in engineering units
ER.28	Overrange / Underrange: ER.28 is displayed alternatively to measured load. Verify that sensor mechanical installation is OK and corresponding to Factory indications. In case perform again Sensor Installation. Calibrate again the 699Plus after the modifications.
ER.30	C pushbutton is detected pressed for more than 3 seconds, when controller is in programming.


APPENDIX H
2 OF 2
LOAD WEIGHING
DEVICE SETUP

MOTOR CALIBRATION PROCEDURE
IT IS ACCEPTED THAT PERSONS CARRYING OUT THIS INSTALLATION HAVE
ALREADY RECEIVED FORMAL TRAINING.
THIS PROCEDURE IS FOR GUIDANCE ONLY.

PREPARATION

ENSURE ALL SAFETY DEVICES ARE INSTALLED AND ARE FUNCTIONING CORRECTLY. IT IS RECOMMENDED THAT BOTH THE PENDANT CONTROLLER AND DDU/SPEAKER BOX ARE USED DURING THIS PROCEDURE.

BEFORE STARTING ENSURE THE VALVE BLOCK IS CORRECTLY SETUP AND THE LIFT IS RUNNING AT RATED SPEED.



FOR BEST RESULTS THE FOLLOWING PROCEDURE SHOULD BE CARRIED OUT WITH APPROXIMATELY 80KG ON THE CARRIAGE.

STEP 1

POSITION LIFT AT BOTTOM FLOOR LEVEL AND ENSURE RESET FLAG IS INSTALLED.

STEP 2

TURN ON SWITCH 1 TO SELECT CALIBRATION MODE AND RESET LIFT CONTROLLER. EITHER BY POWER CYCLE OR USE OF 'RESET' BUTTON ON CARRIAGE.

STEP 3

WAIT FOR THE LEARN LEDS TO FLASH AND A CHARACTER 'C' TO BE DISPLAYED ON THE DDU'S.

STEP 4

PRESS AND HOLD RUN BUTTON; MOMENTARILY PRESS PENDANT BUTTON 4 TO INITIATE CALIBRATION.
(NOTE: RUN BUTTON WILL NEED TO BE MAINTAINED)

THE LIFT WILL AUTOMATICALLY RUN UP APPROXIMATELY 1 METER, STOP AND RUN DOWN APPROXIMATELY HALF A METER.

STEP 5

THE LEARN LEDS WILL FLASH TWICE AND THEN REMAIN ON, THIS CONFIRMS THE PUMP UNIT HAS BEEN SUCCESSFULLY CALIBRATED.

STEP 6

RELEASE RUN BUTTON AND TURN OFF **SWITCH 1** TO COMPLETE CALIBRATION MODE AND RETURN TO NORMAL OPERATION.

STEP 7

REFER TO LEARN MODE PROCEDURE (APPENDIX C) IF FLOOR LEVELS REQUIRE PROGRAMMING.

APPENDIX I
MIDLIFT SL + MOTOR
CALIBRATION PROCEDURE

BEFORE BEGINNING SET-UP GUIDE, ENSURE PLATFORM IS POSITIONED AT APPROPRIATE FLOOR.

Label Neptis Power Door Operator - Quick setup guide

1. Connect the programmer to the door operator.

If this is the first time your digital programmer has been used, it will automatically establish communication with the NEPTIS operator. (Move to step 2).

If your digital programmer has been used previously on a different NEPTIS, it will display the message "NO COMMUNICATION", in which case, please use the following procedure:

- A. Press the SET button for about 5 seconds to enter the programming menu.
- B. Scroll through using the F1 button until you reach the RS485 symbol.
- C. Press the ENTER button to enter the "Serial communication setup" section.
- D. The digital programmer will establish communication with the operator. Once finished it will display the message "---OK--- Automatic Door Acquired".
- E. Press the Exit button to return to the Main Menu.

2. Complete a Learning Cycle.

- A. Ensure the end-cap switch is in Position 1.
- B. Press and hold the SET button for about 5 seconds to enter the main menu.
- C. From the main menu, select the SET UP icon and press ENTER
- D. Enter the password. The default password is "AAAAAAAAAA"
- E. Please complete the set-up as follows:

S.01	=	OFF
S.02	=	ON
S.03	=	ON
S.04	=	OFF
S.05	=	OFF
S.06	=	OFF
S.10	=	ON

- F. The screen will display the following message:

"Operator ready to set up. Press OK to start. A 3 second sound means set up is complete".

- G. Manually unlock the landing door (using lock release key) and press OK.

The door will begin to open, searching for a physical stop. Upon reaching the fully open position (when it hits the physical stop), it will emit a prolonged beep. The door will then close at which point the lock can be released. Learn cycle is now completed.

3. Configure door operation.

Enter the main menu, scroll right once and press ENTER to go into the "Switches and Potentiometers" menu. Adjust the following parameters only.

P.01 - Open Speed	=	30%
P.02 - Close Speed	=	30%
P.05 - Open Pause Time	=	12% (100% = 60secs max)
P.13 - Slowing Distance Closing	=	40%.
P.14 - Closing Assistance Position	=	5%.
P.15 - Closing Assistance Trust	=	50%.
P.18 - Open Distance Vs Physical Stop	=	0%.

Important Note: Do not amend any other parameters.

NAME: J.NICHOLLS	DATE: 24/10/16
CHECKED: M.HOOD	DATE: 24/10/16

MIDLIFT SL+
LABEL NEPTIS
QUICK SETUP GUIDE

Stannah

HEAD OFFICE:
Anton Mill
Andover Hampshire
SP10 2NX England

Tel: 01264 339090 Fax: 337942

DRAWING NO: APPENDIX J

REV: