


Midilift SLplus Platform Lift

(Cabin with hydraulic drive)



Installation Guide

Contents

1	SITE REQUIREMENTS AND TOOLS	5
1.1	Site arrival	5
1.2	Installation tools	Error! Bookmark not defined.
2	SAFETY EQUIPMENT AND PRECAUTIONS	8
2.1	Personal protective equipment	8
2.2	Danger / Warning symbols	8
2.3	General safety precautions	8
3	SETTING PLUMB LINES	9
3.1	Plumbing and marking structure position	9
4	LOWER STRUCTURE INSTALLATION	10
4.1	Preparation for lower installation	10
4.2	Fitting lower corner uprights, base plate and horizontal members	11
4.3	Preparing a 2 stage ram for installation (travel < 3.6m)	14
4.4	Installing a 2 stage ram (travel < 3.6m)	15
4.5	Ram guide rails (3 stage rams only, lift travels ≥ 3.6m)	17
5	SLING INSTALLATION	18
5.1	Car guide rails	18
5.2	Fitting sling to car guide rail	18
5.3	Fitting lower door zone ramp and bottom reset switch bracket	19
5.4	Lower door frame installation	20
5.5	Access ramp (only required when a pit is not available)	22
5.6	Installation of the Trailer Connection Box (TCB)	23
6	STRUCTURE INSTALLATION (CONTINUED)	24
6.1	Attaching the temporary work platform to the sling	24
6.2	Installing next structure level from the work platform	25
6.3	Installing next set of car guide rails	26
6.4	Installing infill panels above the lower door frame	27

7	INSTALLING A 3 STAGE RAM (FOR 2 STAGE RAMS SEE SECTIONS 4.3 & 4.4)	28
7.1	Attaching the chain hoist to the structure and sling	28
7.2	Hoisting the sling and securing it in a raised position	29
7.3	Setting up the ram retaining strap	30
7.4	Connecting the ram to the chain hoist & raising ram	31
7.5	Securing the 3 stage ram in position	32
7.6	Installing the intermediate ram guides, ram guidance assembly & oil reservoir	33
7.7	Installing the Trailer Connection Box (TCB)	34
7.8	Lowering the sling to the pit floor using the chain hoist	34
8	DOOR INSTALLATION	35
9	CONTROL PANEL & TRAILING CABLE INSTALLATION	38
9.1	Installing the control panel	38
9.2	Installing the trailing cable chain	39
9.3	Installing the trailing cable cover and guidance channel	40
9.4	Cable routing and cover panel	41
10	HYDRAULIC PUMP UNIT	42
10.1	Mounting the pump unit	42
10.2	Connecting the pump unit	43
10.3	Bleeding the ram	44
11	SLING INSTALLATION (CONTINUED)	45
11.1	Fitting lower sling braces and cross angle	45
11.2	Attaching the floor assembly	46
11.3	Attaching the support chains	47
11.4	Running clearances	48
11.5	Guide end stop for installation stage (IMPORTANT HEALTH & SAFETY PROCEDURE)	49
12	SECURING THE STRUCTURE	50
12.1	Squaring the structure & fixing it to load bearing walls	50
12.2	Fixing the structure to the building floor	52

13	INTERMEDIATE & UPPER DOOR / FRAME INSTALLATION	53
13.1	Fitting door frame threshold plate	53
13.2	Fitting intermediate / upper door frame	54
13.3	Fastening door frame to building threshold	55
14	UPPER STRUCTURE INSTALLATION	56
14.1	Fitting top corner uprights	56
14.2	Fitting upper structure panels, door frame and door	58
14.3	Installing upper car guides, guide end stops & upper ram guides	59
14.4	Installing the structure ceiling bracing	62
14.5	Landing call station - standard	63
14.6	Landing call station - fire clad	63
15	CABIN FRAME INSTALLATION	64
16	INSTALLING THE LIFT POSITIONING ENCODER	65
17	CABIN INTERIOR INSTALLATION	65
18	HYDRAULIC CONTROL VALVES	66
18.1	Hydraulic control valves - overview	66
18.2	Hydraulic control valves - adjustment	67
19	TROUBLE SHOOTING	68
20	SAFETY CHAIN SWITCH LOCATIONS	69
21	COMMISSIONING	71
22	DOCUMENT HISTORY	73

1 SITE REQUIREMENTS AND TOOLS

1.1 Site arrival

1.1.1. On arrival at the site, the installer should make his presence known to the customer. The installer must comply with any site safety procedures and regulations that are in force.

1.1.2. Before commencing the installation, it is important to ensure that the power supply has been fitted according to the requirements of the builder's work and electrical schedule.

1.1.3. It is important to check that:

- The position of the power supply and route to the trailer connection box are according to the site plan.
- Lift travel, pit depth (if applicable) and headroom dimensions accord with the arrangement drawing.
- An adequately clear working area, free from carpets and furniture, has been provided in all areas in which the lift will travel.
- Piping or cables not related to the lift installation have been adequately protected or re-routed away from the lift path.
- All decor disturbed during the building work has been adequately made good.
- A dedicated single phase 240V power supply, terminating in a 16 amp switched fuse spur unit, has been provided.
- All lift parts have been received and are not damaged.

Should any of the above be incorrect or not available, consult the installation manager.






1.1.4. All carpet areas, walkways and any remaining furniture in the vicinity of the lift is to be protected with dust sheet. Avoid any undue disruption.

1.2 Installation tools

Before using any of the installation tools, it is important to check for damage / corrosion to ensure that each tool is safe to use.

The list below is not all-encompassing and does not include the essential standard hand tools/meters required by installation engineers in a construction environment.

For a full list refer to **Installation Tools Document 6205341**.

Description	Fig.
Plumb lines	
Temporary work platform	
Lower platform support chain	
Support chain anchor brackets	
<p>Electric hoist (500Kg)</p> <p>OR</p> <p>Manual hoist (500Kg)</p> <p>It is vital that the hoist (electric or manual) is properly maintained and checked every 6 months.</p>	

<p>Upper hitch brackets (Attached to the temporary work platform)</p>	
<p>Temporary work platform hanging brackets:</p> <ul style="list-style-type: none"> • Upper pair • Lower pair 	
<p>Dee Shackles x 2</p>	
<p>Removable lifting channel</p>	
<p>Sling locking brackets</p>	
<p>Pendant control box</p>	
<p>Installers DDU & speaker box</p>	
<p>Ram bleeding kit</p>	
<p>Lifting Eyebolt (M16)</p>	

2 SAFETY EQUIPMENT AND PRECAUTIONS







2.1 Personal protective equipment

The following safety equipment is provided for you personal safety.

USE AS REQUIRED AND WHEN INDICATED IN THIS MANUAL.

 Safety gloves	 Safety goggles	 Safety helmet	 Ear protection	 Safety shoes
--	---	--	---	---

2.2 Danger / Warning symbols

 Danger: Electric shock	 Danger: Risk of falling	 Danger: Suspended load	 Caution / Warning	 Weight = xx kg	 Danger: Crushing hazard
---	--	---	--	---	--

2.3 General safety precautions

- Always use personal protective equipment when indicated in this manual.
- Always ensure that electrical equipment is disconnected from the power supply before working on them.
- Do not use any shorting links unless stated otherwise.
- Follow each instruction in this manual and **DO NOT** skip any step as a potentially dangerous situation may arise in doing so.
- Ensure that the **pit prop is in its active position when any work is undertaken below the platform**
- **Ensure that the ultimate limit ramp is positioned/re-positioned correctly during installation, to prevent the platform from being driven out of the car guides and/or the ram guidance channel being driven out of the ram guides.**
- Ensure that lifting aids are considered before attempting team lifts for loads above 25Kg
- Follow general health and safety procedures while lifting heavy loads and working from height.
- Danger / warning signs will indicate when there is a potential risk, pay special attention to these risks and ensure that safe working practices are upheld.

3 SETTING PLUMB LINES

3.1 Plumbing and marking structure position

Before commencing installation of the lift, plumb lines need to be dropped to ensure the lift is positioned correctly.



Starting from one side of the top landing entrance, drop a plumb line and mark its position at the lower floor.

Repeat at the other side of the landing entrance so that a line can be drawn that is parallel with the landing floor.

This needs to be repeated for each landing.

Using the markings made from laying the plumb lines, the floor that protrudes the most will be indicated. Use this landing as a datum.

On smaller travel lifts (up to 5m) it is possible to move the base of the lift into position using a large lever (crowbar). However, the above process is still recommended to ensure that the lift structure will pass through each floor aperture before commencing the installation.



4 LOWER STRUCTURE INSTALLATION

4.1 Preparation for lower installation

Once the landing entrance datum line has been drawn, it is possible to position the first components correctly.

Extend the landing entrance datum line back to the guide wall.



Place the first corner upright against the guide wall and in line (outer edge) with the landing datum line.




NOTE: Be sure to use the correct corner uprights for the lower structure.

They can be identified by two rectangular cut-outs near the bottom; they also have a plate welded flush with one end.

The next corner uprights and horizontal members (HM's) can then be placed in their correct positions.




4.2 Fitting lower corner uprights, base plate and horizontal members

 NOTE: The stop switch must be fitted to the end of the base plate nearest the bottom entrance.

Once parts are near their final position, fix together using M8 screws and contact washers.

To square the lift, measure the diagonal distance between corner uprights, each diagonal should be the same dimension. If not, then adjust their position and check again, repeat until the diagonals are equal.


 NOTE: It is vital that the lift is installed as square as possible to avoid problems later on.

Using a spirit level and supplied packers, ensure that the lower horizontal members and base plate are level. **Note: Packer height may not exceed 20mm at any single location.**

An M16 nut is welded to the base of each corner upright. Use this with an M16 bolt to jack the structure up to allow packers to be placed underneath.


Once the structure has been levelled, unwind the bolts to ensure the weight is supported on the packers and not the M16 bolts.

Once the structure is levelled, pack between the base plate and pit floor directly underneath the ram, car guides & pit prop base plate (these are where vertical loads need to be transmitted to the pit floor).



Panel Installation

Rest the vertical panel extrusions onto the lower horizontal members and fix through the corner uprights in three positions (top, middle & bottom) using M8 x 20mm screws and contact washers.




Composite panels:

Slot infill panels into the vertical panel extrusions from above.

Each panel is separated by the 'H' section extrusion.

Once 3 panels have been installed, fix the next ring of horizontal members, using M8 x 20 screws and contact washers.



NOTE: It is vital that the correct horizontal member is used above the first 3 infill panels on the guide side – this HM can be identified by 2 extra fixing holes (M12) in the centre of the channel which will be used for securing the top of the ram.

Glass panels:

Firstly, place three 30mm tabs of insulating foam into the lower HM channel or 'H' section channel for the glass panel to sit on.

Using suction cups slide one side of the glass panel as far into the vertical panel extrusion as possible (1).


Pivot the glass so that it lines up with the vertical panel extrusion on the opposite side (2).

Slide the glass back so that it is supported either side (3).

Slide the glass panel down into lower HM channel or 'H' section channel (4).

Finally, feed a length of plastic tubing down either side of the glass panel to secure it from lateral movement (5).

Repeat steps (1) to (5) for each individual panel of glass.



Glass >30Kg


Using the panels as a fall arrest barrier:




NOTE: to fit upper panels / glass, use the lower panels as a barrier to safeguard against falling out of the shaft.

Always maintain all 4 sides up to the same level. Ensure that the platform is a **MINIMUM of 900mm** below the uppermost panel.

Always use the panel limit switch tool to avoid accidentally over travelling past the 900mm limit.



4.3 Preparing a 2 stage ram for installation (travel < 3.6m)

 **Section 4.3 is only applicable to lifts with a travel < 3.6m, where a 2 stage ram is used.**
Lifts with a travel greater than 3.6m, use a 3 stage ram....go to section 4.5.

Removing the 3/8" BSP fittings

Lay the ram horizontal on the floor.

Remove the 3/8" BSP quick release male stud coupler, male adapter and bonded seal from the base of the ram. These can be discarded.

Adjusting the rupture valve

Remove the rupture valve from inside the base of the ram. This can be done by inserting pins in the holes and rotating the valve anti-clockwise.

The valve is generally only finger tight.


Using feeler gauges, check the gap of the valve. The gap should be set to **1.6mm** for 2 stage rams on the SLplus.

Note – The gap tends not to be uniform around the valve, so set the gap to an average.


Replace the rupture valve back into the ram base and screw in until finger tight. - **DO NOT OVERTIGHTEN.**

Fitting the 1/2" BSP adapter kit


Once the rupture valve has been set and re-inserted in to the ram, install the components from the supplied adapter kit as shown. The 2 stage ram is now ready to be installed in to the lower structure.



After adjusting & re-inserting the rupture valve, fit the 1/2" BSP adapter kit to the base of the ram



4.4 Installing a 2 stage ram (travel < 3.6m)


 **Section 4.4 is only applicable to lifts with a travel < 3.6m, where a 2 stage ram is used.** Lifts with a travel greater than 3.6m, use a 3 stage ram....go to section 4.5.

Assemble the M12 studding, full nuts, contact washers & half nuts with one of the ram straps as shown. The studding should be wound in until it bottoms out at the rear of the horizontal member.

IMPORTANT - Note the positions where half nuts are used.

Adjust the position of the ram strap until the dimensions shown are achieved. This will ensure the ram is parallel to the structure guide side.


Note - Final checks and adjustment to the ram alignment may be required once the structure is plumbed and secured.

 **IMPORTANT: 2 stage rams must have a 3mm thick spacer fitted to prevent the 1/2" quick release coupling from clashing with the ram location plate.** 3 stage rams do not require the spacer.


Position the 3mm thick ram spacer on top of the ram locating plate on the base plate.

Lower the ram in to position ensuring that the spigot on the ram base passes through the hole in the ram spacer and in to the base plate locating hole.


Orientate the ram inlet towards the hose route.



Dimensions for 3 stage rams are different - please refer to section 7.3



Dimensions are from front face of HM to rear surface of ram strap



2 stage ram ≈ 61kg

Secure the ram with the second ram strap using half nuts, contact washers & full nuts as shown.

IMPORTANT - Note the positions where half nuts are used.


Ensure that the ends of the studding do not protrude in to the running path of the sling. Cut the exposed ends of the studding if necessary.



Check that the ram is plumb to the structure. This can be achieved by measuring at the top and bottom of the ram. The gap between the ram case and the top HM should be 3mm greater than the gap measured between the base plate flange and the ram case.

i.e. DIM TOP = DIM BOTTOM + 3mm

This is due to the extra 3mm thickness of the base plate angle.




4.5 Ram guide rails (3 stage rams only, lift travels $\geq 3.6\text{m}$)



Section 4.5 is only applicable to lifts with a travel $\geq 3.6\text{m}$, where a 3 stage ram is used.
Lifts with a travel less than 3.6m, use a 2 stage ram and do not require ram guides....go to section 5.

Fit the lower pair of ram guides in place, using the M8 fixings provided, as per the illustration.



5 SLING INSTALLATION

5.1 Car guide rails

Fix one 'T' section guide in place using M12 fixings and guide clips.

The lower end of the guide fixes to the base plate with M12 screws, contact washers & nuts (4 off).

M12 guide clips, contact washers & nuts secure the upper end of the guide rail to the first set of guide brackets (2 clips per bracket).



NOTE:
All M12 guide clips must be tightened to a torque of 38Nm.

A visual check must also be made, to confirm that the heel of the clip has made contact with the bracket face (see image).

Degrease the guides and re-lubricate with a thin coat of Fuchs Super Lube grease.




NOTE: Ensure the correct guides are selected - **the lower guides are 2500mm long.**

M12 guide clips, contact washers & nuts – 2 per bracket



Car guide



M12 x 30 hex hd screws, contact washers and nuts – 4 off

5.2 Fitting sling to car guide rail


Move the sling in to the shaft before the door frame is fitted. This allows greater access to manoeuvre the sling in to position.

Locate the sling guide shoes on to the blade of the car guide.



Sling mass ≈ 81kg


Temporarily fasten sling to guide



Remove the guide bracket (indicated in the illustration) to allow the second 'T' section guide to be inserted in to the sling guide shoes.

Once the second guide is in position, re-install the guide bracket and fix the guide in place with M12 fixings at the guide bracket and guide base.

The temporary tie fastenings can now be removed.



5.3 Fitting lower door zone ramp and bottom reset ramp

Once the sling is in position the 'lower door zone ramp' & 'bottom reset ramp' can be positioned and fitted.


Fasten the lower door zone ramp assembly to the car guide using 2 sets of M12 guide fixings – the plunger of the door zone switch should align with the centre of the brass contact plate.

Fasten the bottom reset ramp to the cabin guide rail using 4 off M12 guide clips, contact washers and nuts.

The top edge of the ramp vertical section should be positioned 1100mm above the bottom finish floor level.

Once the platform is operational, the bottom reset ramp should be adjusted such that the platform floor comes to rest flush with the lowest landing.

Coarse adjustment can be achieved by moving the ramp plate up and down the guide. Finer adjustment can be achieved by moving the ramp itself or by moving the switch assembly on the carriage.



5.4 Lower door frame installation

Preparation – cable access hole

Before fitting the door frame, take an approx measurement from the landing threshold to the centre of the slot in the door frame 'Dim A'.


Measure a distance up from the bottom of the call station structure upright that is equal to 'Dim A + Pit Depth' and mark the nearest hole.

Using a step drill open out this hole to 20mm diameter.

NOTE: The enlarged cable hole is required on the call station side only.

Preparation – access ramp (when pit not available)

Loosely fit three M8x20 hex head screws in to the underside of the door frame, ready for the installation of the ramp – refer to section 5.5.



Installing door frame into the structure.



CAUTION:
Door Frames weigh
60Kg.


Consider using lifting aids before
attempting a team lift.

Remove the cover plates on the inside of
the door frame to allow access for fixings.

Position the door frame in between the
corner uprights and use packers under the
frame to ensure the threshold is level (pit
only), then fix back in the positions shown
(on each side of frame).

A spacer plate & fixing plate are used on
the lower fixings. The spacer plate sits
within the rectangular cut out in the corner
upright and the fixing plate sits on top of
this, with the angle flange in contact with
the inside of the corner upright (to stop the
fixing plate from spinning).


NOTE: the door frame sits 20mm off the
lower floor/pit



5.5 Access ramp (only required when a pit is not available)

Slide the ramp in to position and attach it to the underside of the lower door frame using three M8x20 hex head screws.

Note: The fixings can be accessed with a spanner from inside the pit area.




5.6 Installation of the Trailer Connection Box (TCB)



The Trailer Connection Box (TCB) is fitted at this point of the installation on 2 stage ram arrangements only.

For 3 stage arrangements, the TCB is fitted after the ram is installed (to avoid damaging the TCB during hoisting of the ram)...proceed to section 6.




Attach the trailer connection box to the guide side horizontal member using an M8x20 hex head screw and contact washer.

Ensure that the TCB is hanging vertically and then fasten it to the infill panels with four self drill screws through the holes provided in the box.

Note: The TCB is always mounted to the left of the ram.

TCB always mounted on the left

M8 x 20 hex hd screw & contact washer



Self drill fixings at 4 positions

6 STRUCTURE INSTALLATION (CONTINUED)

6.1 Attaching the temporary work platform to the sling




NOTE:
Refer to the separate work platform installation manual to assemble the work platform & ladder correctly and safely.

Fasten the upper hanging brackets to the top of the sling uprights using 3 x M16 fixings per bracket.

Fasten the lower support brackets to the sling uprights using M8 x 20 flange hex hd screws.


Hang the work platform from the temporary hanging brackets at the top of the sling uprights.

Secure the bottom of the work platform to the support brackets using the threaded feet and locking "wing nut".




NOTE:
Always use the lower hook location holes so that the work platform is at its highest position.

Work platform hooks on to upper brackets




Work platform fastened to lower support brackets




6.2 Installing next structure level from the work platform

Working from the installation work platform, join the next set of corner uprights using the joint brackets and M6 csk screws.



Fit the next set of infill panels and horizontal members in position using the method described in section 4.2.



6.3 Installing next set of car guide rails


Using the fishplates provided, attach the next pair of car 'T' section guides.



NOTE: Ensure the correct guides are selected - **the intermediate guides are 1850mm long.**

NOTE: ensure the guides are fixed back to the horizontal members using the guide brackets and guide clips.

It may be necessary to file the front, rear and side faces of the guide blades at each joint to ensure a smooth ride when the cabin guide shoe passes over them.



6.4 Installing infill panels above the lower door frame

The panels & vertical extrusions that lie beneath intermediate and upper door frames need to be cut to length.

Use the formula below and the drawing opposite to calculate the correct cutting length, and then fit using the same procedure detailed in section 4.2.

Panel cut length formula:
 $D = L - 182.0\text{mm}$




Extrusion cut length formula:
 $E = L - 217.0\text{mm}$

As with the lower door frame, a hole in the corner upright needs to be opened out for cable access on the call station side of the door frame.

Take an approximate measurement from the landing threshold to the centre of the slot on the door frame (Dim A), apply this measurement to the corner upright and pick the nearest hole to open out to 20mm. See section 5.4.



For 2 stage arrangements, skip section 7 and proceed to section 8



7 INSTALLING A 3 STAGE RAM (for 2 stage rams see sections 4.3 & 4.4)

7.1 Attaching the chain hoist to the structure and sling

Working from the work platform, place the lifting channel between the car guides so that it rests on top of the upper pair of guide brackets.



NOTE:
Ensure that the guide clips are tightened and the guide brackets are screwed securely to the horizontal member before suspending any load on the channel!

Before attaching the chain hoist, ensure that the protective chain guards are in place on top of the sling. These prevent the chains from damaging the paint on the sling.

Fasten a D-shackle to the lifting eye on the lifting channel, and then suspend the chain hoist from the D-shackle.

Feed the chains through the two chain guards. The control chain and lifting chain should be run down opposite sides to avoid entanglement during hoisting.

Fasten an M16 eyebolt through the central rear hole of the sling mid-channel. Two M16 full nuts should be locked together on the underside of the mid-channel.

Fasten a D-shackle to the M16 eyebolt and attach the lifting hook to the shackle.


Before raising the sling, the pit prop must be installed.

Attach the pit prop leg to the pit prop base using an M16x50 hex hd screw and nyloc nut.




Note: slot in base allows pit prop leg to be inserted. Be careful not to damage the micro-switch!

Secure the pit prop to the base plate using the studs & fixings provided. Position it on the side nearest the lower entrance.




Note: Work platform omitted for clarity




7.2 Hoisting the sling and securing it in a raised position

Using the chain hoist, raise the sling until there is a gap of approx 750mm between the base plate and the sling buffer.




Deploy the pit prop to its active position whenever the sling is raised.

The pit prop has a notch in its upper corner which must locate on the blade of the guide rail. If it does not align properly, small adjustments can be achieved using the slots on the pit prop base. If the pit prop is still misaligned it will be due to incorrect packing under the base plate – add or remove packers until the pit prop leg is parallel to the guide side wall.




Once the sling has been raised to the position shown, it must be locked in place using two locking brackets, one each side of the sling.



Always ensure the locking brackets are holding the sling & the pit prop is deployed before attempting to disconnect the chain hoist!


Once the sling is fastened in place and the pit prop is deployed, the lifting chain can be disconnected from the sling ready for hoisting of the ram.



7.3 Setting up the ram retaining strap

Assemble the M12 studding, full nuts, contact washers & half nuts with one of the ram straps as shown. The studding should be wound in until it bottoms out at the rear of the horizontal member.

IMPORTANT - Note the positions where half nuts are used.




Note: Sling omitted for clarity

Adjust the position of the ram strap until the dimensions shown are achieved. This will ensure the ram is parallel to the structure guide side.

Note - Final checks and adjustment to the ram alignment may be required once the structure is plumbed and secured.

Dimensions are from front face of HM to rear surface of ram strap



Dimensions for 2 stage rams are different - please refer to section 4.4

7.4 Connecting the ram to the chain hoist & raising ram

Attach the ram lifting eye assembly to the top of the ram using the M12 ram/carriage bolt and an M8 x 16 hex head screw.

Attach a D-shackle to the ram lifting eye.



Drop the lifting chain down behind the mid-channels of the sling.

Safely manoeuvre the ram such that the lifting eye assembly is directly below the lifting chain.

Connect the lifting hook to the D-shackle.




3 stage ram ≈ 102kg



Raise the ram up using the chain hoist, occasionally moving the base of the ram towards the structure (to ensure that the lifting chain remains as near vertical as possible).

Once the ram is suspended above the base plate, carefully lower the ram in to position ensuring that the spigot on the ram base passes in to the base plate locating hole.

Orientate the ram inlet towards the hose route.



7.5 Securing the 3 stage ram in position




Secure the ram with the second ram strap using half nuts, contact washers & full nuts as shown.


IMPORTANT - Note the positions where half nuts are used.

Ensure that the ends of the studding do not protrude in to the running path of the sling. Cut the exposed ends of the studding if necessary.

Once the ram is secure, the chain hoist can be disconnected ready for the ram guidance assembly to be fitted.

Remove the ram lifting eye assembly.



 **Check that the ram is plumb to the structure. This can be achieved by measuring at the top and bottom of the ram. The gap between the ram case and the top HM should be 3mm greater than the gap measured between the base plate flange and the ram case.**

i.e. DIM TOP = DIM BOTTOM + 3mm

This is due to the extra 3mm thickness of the base plate angle.

7.6 Installing the intermediate ram guides, ram guidance assembly & oil reservoir

Intermediate Ram Guides


Install subsequent pairs of ram guides, fastening through the guide, joiner and horizontal member, using M8 fixings.

Note: A joiner should also be fitted to the top of all guide sections despite the ram guides not extending to the top of the structure. This ensures vertical alignment of the ram guides.


Note: Reference should be made to the builders' work drawing for all guide lengths and their corresponding positions.

Ram Guidance Assembly

Insert the ram guidance assembly in to the blades of the ram guides and slide it down on to the ram cap.

 **IMPORTANT: The ram guidance assembly must be installed with the angles pointing up.**

Fasten the ram guidance assembly to the ram cap using 4 off M8x12 hex head screws and contact washers. The ram cap will need to be rotated to align with the ram guidance assembly – ensure the bleed screw is orientated towards the cabin.


 **IMPORTANT: Ensure that the bleed screw on the ram cap is facing towards the cabin!**

Note: Packers are pre-installed on the ram guidance assembly. These can be removed if necessary to achieve a running clearance of 1-2mm between each guide blade and guide shoe. A slot is provided to lever the packers out using a screwdriver.

Oil Reservoir

Connect the overflow pipe to the elbow at the top of the ram. Fasten the oil collection bottle and pipe to the ram using cable ties.


Note: Do not over-tighten the cable ties around the pipe as this may restrict the flow in to the bottle.



7.7 Installing the Trailer Connection Box (TCB)

Now that the ram is installed and the sling is raised up out of the way, the Trailer Connection Box (TCB) should be fitted.


Refer to section 5.6 for installation method.



Refer to section 5.6 for details of installing the TCB

7.8 Lowering the sling to the pit floor using the chain hoist

Re-connect the chain hoist to the sling and take up the slack in the lifting chain ready for removal of the locking brackets.




CAUTION! DO NOT REMOVE THE LOCKING BRACKETS UNTIL THE CHAIN HOIST IS SUPPORTING THE SLING!

Once the weight of the sling is being supported by the chain hoist, remove both locking brackets from the sling/ram guides.

Using the chain hoist, lower the sling on to the base plate.

Remove the chain hoist, lifting channel, shackles etc.

Remove the protective chain guards from the top of the sling and discard.



8 DOOR INSTALLATION

To prevent people from entering the space below the platform during installation, it is recommended that the lower door is fitted at this stage.

Glazed Doors

Loosen the fixings on the upper pivot pin and slide it down to its lowest position.

Place the door spacer over the pivot hole at the bottom of the door frame.



CAUTION:
Door assemblies weigh over 70Kg.

Consider using lifting aids before attempting a team lift.

Manoeuvre the door so the lower pivot pin slots through the door spacer and into the bush in the door frame.

Line up the upper pivot pin with the pivot hole in the top of the door frame.

Slide the upper pivot pin up into the bush in the door frame.

Fasten the upper pivot pin by re-tightening the M5 fixings.


Clip the curved 'U' section to the edge of the door.



NOTE: Once the 'U' section has been fitted, it is very difficult to remove without causing damage.

Fit the handle spigots to the door with the countersunk fixings provided.

Fasten the handle to the spigots using the grub screws provided.




Fire Doors

Before fitting the fire door, the intumescent strips, handle, contacts and the door lock plate need to be fitted.

A slam plate will also need to be screwed to the slam side edge of the door, but it is best to fit this once the door has been fitted to the frame.

Cutting details for the 30mm wide intumescent strips for both the 30-minute door and the 60-minute door are similar as shown.





CAUTION:
Door assemblies weigh
over 70Kg.

Consider using lifting aids before
attempting a team lift.


To fit the door, use packers to raise the door to the correct height, then line up the hinges with the holes in the door frame upright.

Fix the door to the frame using M5 x 16 CSK screws. A 2mm thick shim should be placed between each hinge and the door frame.

Note: 1.2mm shims are also provided – these can be used in place of the 2mm shims if the slam edge of the door is tight to the frame.


Fix the spacer plates to the slam side of the door frame using self drill csk screws. The plates are used to remove any gaps and increase the fire resistance of the assembly.

There should be a 3mm nominal gap on the hinge side and a 5mm nominal gap above and below the door. If the gap above any fire door exceeds 5mm then a spacer strip should be fitted to the underside of the header.



M5x16 CSK screws
(4 per hinge)


2mm shim
(1 per hinge)



Fit header spacer with self-drill
CSK screws if the top gap
exceeds 5mm.

To fit door lock
spacer, remove
security screws
& refit

Fire door spacers
(2 x 3mm & 2 x 1.6mm)




9 CONTROL PANEL & TRAILING CABLE INSTALLATION

9.1 Installing the control panel


Fit the control panel assembly to the sling using 8 off M5x12 flange hex head screws.


Feed the trailing cables around the front of the sling upright and secure them using cable ties.

 Ensure the cables do not protrude more than 15mm in front of the sling upright as this could prevent the cabin side panels from fitting.

Pass the rectangular cut-out of the trailing cable support bracket over the trailing cables and attach the bracket to the bottom right hand side of the sling, using 2 off M5 contact washers and nuts. **The trailing cables run behind the support bracket.**

Attach the trailing cable chain to the support bracket using 2 off M5x16 hex head screws, contact washers and nuts.

 Cables must be routed neatly inside the control panel horizontal channel & cable tied to prevent any possibility of them catching on shaftwork items.



Route cables neatly around the back of the control panel horizontal channel & fasten to prevent catching on shaftwork items

9.2 Installing the trailing cable chain

The trailing cable fixing channel spans either a horizontal member and 'H' section or two 'H' sections (depending on the lift travel).

The fixing channel should be positioned so that the top end of the trailing cable chain is at a height equal to **half the lift travel + 200mm**. A number of fixing holes are provided in the channel to allow the chain end to be moved up or down to the desired position.


Fasten the top end of the trailing cable chain to the fixing channel using 2 off M5x12 flange hex head screws.

Cable tie the trailing cables to the fixing channel.


Feed the trailing cables over the top of the fixing channel and back down behind it, then fasten the fixing channel to the horizontal member/'H' section(s) using self drilling screws.

Note: The right hand edge of the channel butts up against the corner upright.

Ensure that the loop at the bottom of the chain is clear of the base plate.



If the bottom landing entrance is the same side as the trailing cables, the chain loop will hang above the pit stop switch. Ensure sufficient clearance to prevent the chain loop from striking the stop switch!



9.3 Installing the trailing cable cover and guidance channel

The trailing cables run back down the guide side wall behind a cover and guidance channel assembly and exit in to the guide side horizontal member.


On lift travels less than 3.6m one assembly is provided; for travels above 3.6m two assemblies are provided.



Measure the distance from the underside of the trailing cable fixing channel to just above the cable access cut-out in the base horizontal member. Cut the cover/guidance channels to lengths that cover this distance. The cut edge should be positioned at the bottom.

Fasten the static cables in to the rear of the cover channel using sticky pads and cable ties. This ensures the cables don't get caught between the channel and the structure wall during fitting.

Feed the chain in to the guidance channel(s) and then fasten the channel(s) to the structure wall using self drilling screws.

The guidance channel(s) should be vertical and aligned central to the fixing channel.

 When the chain is fastened on the upper 3 pairs of holes of the fixing channel, a short length of guidance channel is provided to guide the chain when the lift is at the top floor.



9.4 Cable routing and cover panel


The trailing cables should be routed inside the bottom guide side horizontal member and exit directly under the Trailer Connection Box (TCB).

Feed the cables vertically up through the cable entry hole in the underside of the TCB.

Terminate the trailing cables in accordance with the SLplus wiring manual.

Note: The ultimate limit switch and door zone feed cables need to be connected in to the control panel as well.

Fit the cable cover over the top of the trailing cables and secure in position with self drilling screws.



10 HYDRAULIC PUMP UNIT

10.1 Mounting the pump unit

Position the pump unit as per the builders work drawing.

A working area in front of the pump unit must be available – see diagram for minimum dimensions.

* For existing buildings the clear height may be reduced to a minimum of 1800mm but suitable warnings must be placed near the pump unit.


The pump unit must be fastened in position using the fixings and isolation pads provided.

Apply the self adhesive emergency release label to the pump unit.

Secure pump unit to wall using supplied fixings & isolation pads



Pump unit: empty ≈ 30kg
filled ≈ 60kg



Note: Dimensions in mm

**HYDRAULIC MIDILIFT
EMERGENCY RELEASE PROCEDURE**

6100677

FOR USE BY AUTHORISED PERSONNEL ONLY
To be used only in an emergency by authorised persons who have had instruction. It is dangerous for any other persons to attempt this procedure.

Lift Lowering Procedure


1. Switch OFF the lift mains electrical supply.
2. Ensure all lift landing doors are closed and locked.
3. Locate the RED manual lowering knob. The knob can be either pulled, pushed or turned to operate depending on the unit that has been supplied.
CABIN models only: these are equipped with two knobs - see diagram on right to locate the correct knob.
4. Inform the trapped passengers within the lift that you are about to lower the lift and request they remain clear of the sides. (Safety edges are inoperative during this operation).
5. Operate the RED manual lowering knob to lower the lift. The lift will stop when the knob is released. Release the knob when the lift is touching the lower floor.
6. Replace and lock the power pack enclosure lid.

Passenger Release Procedure

Important: Passengers should always be evacuated at the lowest level. It is potentially dangerous to release passengers at any other levels.

7. Once the lift is at the lowest floor level, remove the lock cover (located in the lower door frame).
8. Using the door lock release key, insert the key and turn it 90° until the latch releases the door.
9. Manually open the lift door and release the passengers.
10. Once the lift is vacated, leave the lift mains electrical supply switched OFF, close and lock the lift door and telephone your local service branch.

Location of lowering knob on Cabin model




Apply emergency release label

10.2 Connecting the pump unit

Connect the hose to the pump unit and route the hose through the guide side horizontal member to the base of the ram – **DO NOT CONNECT TO RAM AT THIS STAGE!**

Run the cable from the pump unit to the trailer connection box and terminate in accordance with the wiring manual.

Electrically connect the pump unit to the 240Vac power supply as per the wiring manual.

 **NOTE:** Ensure hose and cable are routed clear of sling and cabin floor to prevent damage when lift is at the lowest level.

Fill the tank with the correct grade oil, up to the maximum level indicator.


Connect the pendant control box and set the controller to installation mode as per the wiring manual.

Insert a spare male quick release fitting in the end of the hose and prime the hose by running the pump for a few seconds until clean, air-free oil flows in to a suitable container. Stop the pump and release the male quick release fitting. This process minimises air in the hydraulic system.

Connect the quick release coupling to the base of the ram ensuring it is fully engaged.

Note: If the coupling fails to engage easily on a 2 stage ram, it could be due to the 3mm ram spacer being missing (see section 4.4) or pressure in the hose (decrease pressure by pressing the emergency release button briefly).

Any excess hose can be loosely coiled around the motor casing.




10.3 Bleeding the ram

Align the hole in the top stage of the ram with the hole in the ram cup.

Using the pendant control box, run the pump to drive the ram up in to the ram cup.

Insert the retaining bolt and tighten.

Run the platform up approximately 250mm. This places the bleed points at easily accessible heights and eliminates the possibility of a shearing hazard.



The platform will descend slowly during bleeding – keep all limbs clear of moving parts.

Whilst the descent speed of the platform will be slow and controlled during bleeding of the ram, ensure that limbs are not exposed to a shearing hazard.



Particular attention should be given to the shearing potential between sling cross members, the work platform and shaftwork items (such as the ram, its support brackets and TCB). On 3 stage rams the ram guidance channel presents an additional potential shearing hazard with fixed items in the shaft.

Locate the bleed points on the ram. 2 stage rams have two bleed points that require a mating bleed nipple and pipe. 3 stage rams have three bleed screws which are opened and closed using a spanner.

Note: Sections of the ram which are unguided are able to rotate and so the bleed point may not always be facing forwards. The ram section can be rotated by hand to bring the bleed point to the front.

Bleed each section of the ram in turn, until clean, air-free oil flows. Re-close the bleed point each time. If a ram section fully closes before all air is expelled (or the platform comes to rest on it's buffers) the platform should be raised again and the process repeated. Each ram section should have equal extension when bleeding is complete.

Once all air is expelled, ensure all bleed points are closed and wipe away any oil residue.



Note: 3 stage ram shown
(2 stage ram has only two bleed points)

Bleed points

If attempting to rotate a section of ram whilst the lift is in motion (to access bleed points), pay attention to possible shearing hazards.

11 SLING INSTALLATION (CONTINUED)


11.1 Fitting lower sling braces and cross angle

Before fixing the lower sling cross angle and braces, raise the sling up (about 100mm) and rest on packers under each upright. This provides access to fixing bolts on the underside of the floor (needed in the next section).

With the sling in the raised position, fix the cross angle in place using M8 (upper) & M5 countersunk (lower) fixings provided. The cross angle should be mounted centrally to the sling.

Fasten two (of the four provided) diagonal braces between the sling uprights and the lower cross angle, using M8 fixings. Ensure that the lower end of the brace fixes to the rear face of the sling cross angle.

Note: The remaining two diagonal braces are fitted later on when the upper cross angle is fitted.




11.2 Attaching the floor assembly

Before fixing the floor frame in place it is important to check that all safety edges are present and in the correct positions (a safety edge is required on each entrance side).

Bolt one side of the floor frame to the lower sling cross angle using M12 fixings.

Fasten the lower hitch brackets to the remaining two corners of the floor frame using M12 fixings as shown.



11.3 Attaching the support chains

Fix the upper hitch brackets to the support beams of the temporary work platform, using M12 x 100mm studs + fixings.

Attach each support chain between the upper and lower hitch brackets using the latched hooks on either end of the chains.


Place the steel 'under floor plate' into the floor frame. The plate is handed by the 5 holes - ensure the holes in the plate align with the holes in the frame corners and diagonal brace. This conceals the underside of the floorboard.

Finally place the wooden floor board into the floor frame.

To avoid damaging the floor covering during installation, the board should be inserted with the finished surface facing down.



When the lift is being commissioned it will be necessary to turn the wooden floor board so that the floor covering is facing up. The board must then be screwed in position using self tapping screws through the four corners and centre of the floor frame assembly.





11.4 Running clearances

Once the sling is in its final position, adjustments need to be made to ensure the sling sits square within the shaft.


Add or remove slider packers, on either side of the sling, until there is a gap of approximately 0.5mm between the 'T' section guides and the sliders on the sling.

Ensure that there isn't excessive "rocking" of the sling when weight is transferred from one side of the platform to the other.



A gap of approximately 27mm should be present between the floor corner brackets and the corner uprights.

The gap between the floor safety edge and the corner uprights should be approximately 13mm.



11.5 Guide end stop for installation stage (IMPORTANT HEALTH & SAFETY PROCEDURE)




WARNING! BEFORE ATTEMPTING TO RUN THE PLATFORM THE FOLLOWING SAFETY PROCEDURE MUST BE ADHERED TO!!!

To ensure that the platform isn't driven past the end of the guides during installation, the ultimate limit ramp must be positioned 300mm from the top of the car guides and the limit switch tested for correct functioning.


DO NOT RELY ON THE ULTIMATE LIMIT SWITCH TO STOP THE PLATFORM - IT IS TO BE REGARDED AS A SAFETY SYSTEM. THE RUN UP BUTTONS SHOULD BE RELEASED PRIOR TO THE ULTIMATE LIMIT RAMP BEING REACHED.

As further sections of car guide rail are installed, it will be necessary to move the ultimate limit ramp to the same dimension on the upper car guide rail.

Note: In addition, on 3 stage ram arrangements, the ram guides should be built up as high as possible during installation to ensure that the ram guidance assembly does not become driven out of the ram guides.



300mm MINIMUM




12 SECURING THE STRUCTURE

12.1 Squaring the structure & fixing it to load bearing walls

As the running clearances of the lift are small, it is vital that the lift is as square as possible to avoid problems at a later stage.


On longer travel lifts the guide side will need to be fixed back to a supporting wall as the structure is being built (do NOT wait until the structure is completed before fixing back as it may become unstable). Check builders work drawings for fixing positions.

Before fixing back, ensure that the lift is square and vertical using plumb lines, spirit level and measuring the diagonal distances across the corner uprights.



Jacking brackets


Use the jacking brackets provided to aid with squaring the lift, these can be used to push / pull any corner of the structure until square.



To fit the jacking brackets:

Firstly, ensure access to the outside of the shaft is possible (in the area in which the jacking bolt will be positioned). The best way to achieve this is to fit the jacking brackets before the laminated panels.

Feed the jacking bracket into the corner upright (ensure that it has been oriented correctly as it will only feed in one way).





Once in position, temporarily fix in place using M8 fixings into the pre punched holes in the corner upright (the bolts screw into the vertical panel extrusion, through the corner upright).

With the bracket fixed in position, mark the position of the threaded hole onto the inside of the corner upright.

Remove the bracket and drill a 13.0mm hole. The bracket can then be replaced and a piece of M12 studding can be threaded into the threaded hole in the jacking bracket. Lock two nuts on the end of the M12 studding to enable you to use a spanner to wind the studding in or out.

Thread the piece of studding through the corner upright until there is enough visible thread on the outside of the structure to fit the spreader plate.

The studding can then be wound in or out to plumb the structure.

This process can then be repeated, but with the jacking bracket upside down to give adjustment adjacent to the first fixing.

Repeat this for each corner upright.

Shaft fixing brackets


Use the shaft fixing brackets to fix the guide side of the lift back to a load bearing wall:

Use the fixing positions indicated on the builders work drawings to position the fixing brackets. Once in place, use the slot at the back of the bracket to mark the position for a hole onto the laminated panel.

Move the bracket and drill a clearance hole (min $\varnothing 20\text{mm}$).


Fix the guide side wall into the shaft (load bearing) wall using either chemical fixing of coach bolts.

By placing a nut either side of the shaft fixing bracket, the lift can be pushed in or out until plumb.



12.2 Fixing the structure to the building floor

After ensuring that the lift enclosure is correctly positioned, square and plumb, secure the base of each corner upright to the floor of the building with supplied fixings. Tighten each fixing to a torque of 25Nm.



13 INTERMEDIATE & UPPER DOOR / FRAME INSTALLATION



13.1 Fitting door frame threshold plate

Assess the need for a threshold plate. If one is required, ensure that it is fixed to the door frame **before** the door frame is installed. The threshold plate should be positioned so that it is flush with the entrance.

The angle on its own will span a gap of up to 20mm, whilst the extended plate can do up to 100mm.

In order to fit the angle to the door, remove the lower cover plate and slacken off the three M8 screws (which hold the cross member to the door frame). Slide the infill angle between the cross member and door frame and re-tighten the M8 screws.

If a gap greater than 20mm is to be spanned, fix the extended plate to the angle using 4.8mm dome head rivets.



13.2 Fitting intermediate / upper door frame

Position the door frame so that it sits on top of the cut composite panel, with the door frame threshold level flush with the building finish floor level.


Using M8 fixings, fix the door frame in place using the slots provided (see diagram).



CAUTION:
Door Frames weigh
60Kg.

Consider using lifting aids before attempting a team lift.

Note:
Some configurations of door frame (shown) require a self drill screw to fix the middle of the hinge side upright to the corner upright.



13.3 Fastening door frame to building threshold


Before fixing the structure back to the threshold, firstly check that the lift is square and plumb. Then drill through either the lower cross member of the door frame (shown) or through each door frame side corner upright and into the landing threshold.

Using the fixings provided (either chemical fixing or coach bolts), bolt the structure to the landing, placing a nut between the door frame / corner upright and the landing threshold to allow the lift to be jacked in or out. Use a spreader plate on the inside face of the fixing to spread the load over a larger area.

These fixings must be repeated at every landing threshold (not including the bottom floor).

Note: If there isn't enough clearance for a nut between the corner upright and the landing threshold, use packers instead.

Fit the door following the same procedure as the lower door (refer to section 8).



14 UPPER STRUCTURE INSTALLATION


14.1 Fitting top corner uprights

The top sections of corner upright are pre-cut in the factory to a length to suit each specific installation.

Ensure that the corner uprights are installed the correct way up – the lower end of each corner upright can be identified by four countersunk holes.





If the available headroom is greater than 2800mm there will be enough room to install the corner uprights in the same manner as the intermediate uprights.

Note: Two different stiffeners are used – see illustration for identification & location details.



If the headroom is less than 2800mm it will be necessary to install each corner upright in the following sequence:

- a) slide joint bracket in to open end of structure & allow it to rest on the welded gusset
- b) insert stiffener in to the top of the corner upright to be fitted & allow it to rest on the welded gusset
Note: Two different stiffeners are used – see illustration on previous page for identification & location details
- c) position the corner upright above the structure & align it, then slide the joint bracket up in to position and fasten with 8 off M6x25 countersunk screws
- d) slide the stiffener up to the top of the corner upright and temporarily fasten in position with a cable tie
Note: The stiffeners will be screwed in place when the upper ring of cross members are installed.





14.2 Fitting upper structure panels, door frame and door

The upper section of the structure is constructed in the same manner described in section 4.2.


For door frame installation refer to section 13.

For door installation refer to section 8.



Refer to the dimensions on the builders work drawing to identify the upper cut panels and to obtain the cutting lengths for the upper vertical panel extrusions.

The upper ring of horizontal members are fastened with M8 x 20 screws and contact washers passing through the four corner stiffeners.




14.3 Installing upper car guides, guide end stops & upper ram guides

Upper car guides


The upper car guides are pre-cut in the factory to a length to suit each specific installation and have a hole drilled in the blade near the top of the guide.

Using the fishplates provided, attach the upper pair of car 'T' section guides.

NOTE: ensure the guides are fixed back to the horizontal members using the guide brackets and guide clips.



Guide end stops


 **IMPORTANT! THE GUIDE END STOPS MUST BE FITTED TO THE TOP END OF EACH CAR GUIDE TO PREVENT EXCESSIVE OVERTRAVEL OF THE CABIN.**

In the unlikely event of the ultimate limit switch failing to stop the lift, the guide end stops provide a physical stop to prevent the cabin being driven out of the guides.

Slide the end stop assembly over the blade of the upper car guide and align it with the pre-drilled hole in the guide blade.

Fasten the end stop assembly using the M10 screw and nyloc nut provided.

Repeat this process with the second end stop assembly, on the other car guide.



Upper ram guides (3 stage rams only)

The upper ram guides are pre-cut in the factory to a length to suit each specific installation and each have a pair of holes drilled near the top for fastening back to the upper horizontal member.


Attach the upper ram guides to the intermediate ram guide sections using the joiner and fixings provided.

The top end of the upper ram guides are fastened directly to the upper horizontal member with a total of four M8 screws and contact washers.

Note: A guide joiner is not used at the upper ring level.

Ultimate limit switch ramp

Once the car guides, ram guides and end stops are in place the ultimate limit switch ramp can be moved up to its final position. The ramp should be mounted at a height such that the ultimate limit switch operates when the lift is 50mm(+/-10) above the upper finish floor level.



Note: A guide joiner is not fitted at the upper HM connection


14.4 Installing the structure ceiling bracing

Structure ceiling bracing


The top of the structure must always be fitted with diagonal braces.

The braces fasten to each corner upright stiffener using M8x20 hex head screws, contact washers and nuts. A further M8 fixing must be fastened through the hole where the two braces cross in the centre of the structure.

If the upper ring of horizontal members are not perfectly square it may be difficult to pass the corner fixings through the holes. Extra holes are provided in the corner upright stiffener and cross braces to allow a podger to be used to lever them in to position. The corner fixings should be fastened in the outermost holes; the innermost holes are for the use of a podger or similar.



Corner fixings fasten through the outer holes. Inner holes are provided for insertion of a podger to make alignment easier.



14.5 Landing call station - standard

Note: The cable looms are cut to specific lengths to suit each call station position. Ensure the correct loom is used at each landing so that it is long enough to route to the trailer connection box.


Feed a 12 core cable through the pre-drilled hole in the corner upright and the door frame upright.

At landings where a keyswitch is fitted, it is also necessary to run a 2 core cable back to the trailer connection box.

Follow the SLplus wiring manual for connecting the call station and lock assembly.

Remove end caps to give access to the fixing holes. Fasten the call station body to the door frame upright using M5 tamperproof fixings.

Refit the end caps using the M3 socket screws provided.




14.6 Landing call station - fire clad

Fit a back box to the corner upright using two large self drilling screws.

Drill a Ø20 hole through the back box and into the corner upright. Fit a rubber grommet and feed the call station cables through.

The call station can then be fitted in the same manner as detailed in section 14.5 above.

If the cladding has been fitted, drill a Ø25 hole through the cladding, in line with the lock release. Insert the emergency release tube and screw on the bezel.



15 CABIN FRAME INSTALLATION


The cabin frame can now be constructed in the same way as detailed in the XLplus installation manual with the following exceptions:

Load weighing sensor

The load weighing sensor for the cabin overload system is mounted on the top edge of the cabin support angle using the M6 fixings supplied.

Route the cable around the cabin support beams, down the sling upright and plug it in to the load weighing control box.

Ensure the cable is tied back neatly so that it cannot catch on any moving parts when the lift is in motion.




16 INSTALLING THE LIFT POSITIONING ENCODER

The lift positioning encoder system can now be installed in the same way as detailed in the XLplus installation manual with the following exception:

Upper bracket - encoder belt

The upper bracket for the encoder belt should be attached just below the highest guide bracket.




17 CABIN INTERIOR INSTALLATION

The cabin interior can now be installed in the same way as detailed in the XLplus installation manual with the following exception:

Place the roof brace diagonally across the two cabin support beams. Fasten the brace in position with two M5 flanged hex head screws in to the tapped holes in the support beams.

Note: The folded angle of the roof brace should face downwards so that it does not clash with the structure bracing (when the lift is at its uppermost position).



18 HYDRAULIC CONTROL VALVES

18.1 Hydraulic control valves - overview

The SLplus is equipped with two solenoid operated down valves: the main down valve (D) and an additional safety valve (DLV) which will hold the lift stationary if the main down valve (D) fails to close for any reason. Each valve has its own independent control signal.

Safety control

The safety valve (DLV) is a basic valve which is either fully open or fully closed. DLV **does not** control the speed of the cabin.

Speed control

The main valve block controls the upwards soft start and stop, the down soft start, rated speed and stop. The unit is pressure compensating to achieve a constant down speed under all load conditions. Rated speed upwards is not adjustable.

Valve control sequence

To permit a smooth start, it is necessary to open DLV a short time before D.


DLV and D are both held open during travel of the lift.

To permit a smooth stop, it is necessary to keep DLV open for a short time after D has closed at the end of a down journey.

Refer to signal timing sequence on next page for further details.

Notes:

1. The valve block has two manual lowering valves fitted. The manual lowering valve nearest to the front of the pump unit is redundant on this system (due to L10 being normally closed). Manual lowering must therefore be achieved by operating the lowering valve located towards the rear of the pump unit.
2. No pressure switches are fitted to the valve block; load weighing is achieved using a load cell mounted on the sling.
3. In the event of D failing to close at the end of a down journey the lift will descend at rated speed away from the floor level for 1.5 secs until DLV closes and brings the lift to rest. At the lowest landing the cabin will rest on its buffers



18.2 Hydraulic control valves - adjustment

Adjustments UP

The valves have already been set, but some on site adjustment may be required.

Up Bypass: When the pump is started, the unloaded platform should remain stationary at the floor for a period of about 1 second before starting upwards. The length of this delay is according to the setting of adjustment **1** 'In' (clockwise) shortens the delay, 'out' (anti-clockwise) lengthens the delay.

Up Stop: At floor level, the pump-motor is de-energized. The stop may be abrupt depending on load and speed of approach. No adjustment possible.

No adjustment possible.

S, Relief Valve: 'In' (clockwise) produces a higher, 'out' (anti-clockwise) a lower maximum pressure setting. After turning 'out', open manual lowering **H** for an instant to decrease pressure before re-checking.

Important: When testing relief valve, do not close main shut off valve sharply.

Adjustments DOWN

The valves have already been set, but some on site adjustment may be required.

Check electrical operation before changing valves settings.

Down Acceleration: Solenoid **DLV** is energised 1.5 secs before solenoid **D**. During this period the lift is held stationary by **D**. When solenoid **D** is energized, the car will accelerate downwards according to the setting of adjustment **6**.


'In' (clockwise) provides a softer down acceleration, 'out' (anti-clockwise) a quicker acceleration. Pre-adjustment: **6** should be turned all the way in and then solenoid **D** energized. Turn **6** slowly back out until the car accelerates downwards.


Down Speed: With solenoids **DLV** and **D** energised as above, the down speed of the platform is according to the setting of adjustment **9**. 'In' (clockwise) provides a slower down speed, 'out' (anti-clockwise) a faster down speed.


Down Stop: At floor level, solenoid **D** is de-energized causing the car to stop. No adjustment necessary. 1.5 secs after solenoid **D** is de-energised, **DLV** is de-energised.

H, Emergency lowering valve: 'out' (anti-clockwise) allows the car to be lowered by hand. Closes automatically on release.

KS: Some units may be fitted with a slack rope valve. This is not required on the Midilift but may still need to be adjusted. If an empty platform will not descend when **DLV** and **D** are both energised, turn **KS** anti-clockwise until the platform starts to move, turn another half turn to allow for cold conditions.



Key:
 = energised



SLplus timing sequence




19 TROUBLE SHOOTING			
Problem	Possible fault	Possible solution	
<ul style="list-style-type: none"> Specific fault code displayed on DDU's 	<ul style="list-style-type: none"> Codes A to F and R 	<ul style="list-style-type: none"> Refer to 'Fault Code List' in SLplus wiring manual 	
<ul style="list-style-type: none"> No Power 	<ul style="list-style-type: none"> Loss of power to the building 	<ul style="list-style-type: none"> Contact electricity supplier 	
	<ul style="list-style-type: none"> Circuit breaker (MCB) tripped 	<ul style="list-style-type: none"> Reset MCB 	
	<ul style="list-style-type: none"> Isolation keyswitch turned off 	<ul style="list-style-type: none"> Turn isolation keyswitch (3 position) to 'ON' position 	
<ul style="list-style-type: none"> No Movement 	<ul style="list-style-type: none"> Both Directions 	<ul style="list-style-type: none"> Safety chain broken 	<ul style="list-style-type: none"> Identify point at which safety chain is broken, identify problem, reset safety switch and re-test.
		<ul style="list-style-type: none"> Door not closed 	<ul style="list-style-type: none"> Close all doors & ensure all locks are fully engaged
		<ul style="list-style-type: none"> Cabin safety edge operated/sticking 	<ul style="list-style-type: none"> Remove obstruction/
		<ul style="list-style-type: none"> Light ray activated 	<ul style="list-style-type: none"> Clear obstruction
		<ul style="list-style-type: none"> Motor thermal overload tripped 	<ul style="list-style-type: none"> Reset overload (located on terminal box inside pump unit)
		<ul style="list-style-type: none"> Main shut off valve closed 	<ul style="list-style-type: none"> Re-open main shut off valve
		<ul style="list-style-type: none"> Ultimate limit switch activated 	<ul style="list-style-type: none"> Lower lift with manual lowering valve, adjust ramp position & reset switch
		<ul style="list-style-type: none"> Lift overloaded 	<ul style="list-style-type: none"> Remove excess load Reset overload limit on LCA controller (located on the sling)
	<ul style="list-style-type: none"> Up only 	<ul style="list-style-type: none"> Pump running but will not raise cabin 	<ul style="list-style-type: none"> Check for excess payload Adjust relief valve if necessary Main down valve (D) energised - check feed to D Main down valve stuck open - check for contamination or replace D
			<ul style="list-style-type: none"> Down only
<ul style="list-style-type: none"> Poor ride quality 	<ul style="list-style-type: none"> Damaged guides 	<ul style="list-style-type: none"> Identify damaged area of guides and file flat. 	
	<ul style="list-style-type: none"> Rough guide joints 	<ul style="list-style-type: none"> Identify rough guide joint and file flat. 	
	<ul style="list-style-type: none"> Poor start, acceleration or stopping 	<ul style="list-style-type: none"> Refer to valve adjustments on previous page 	

<ul style="list-style-type: none"> Lift stops outside floor level tolerance ($\pm 10\text{mm}$) / Ultimate limit activated 	<ul style="list-style-type: none"> Floor levels incorrectly set up 	<ul style="list-style-type: none"> Re-teach floor levels
	<ul style="list-style-type: none"> Journey timer tripped 	<ul style="list-style-type: none"> Check setting of bit switch 2 (on pcb on cabin mounted control panel): Off=30secs, ON=60secs
	<ul style="list-style-type: none"> Timing belt pulley not connected to encoder shaft 	<ul style="list-style-type: none"> Tighten the grub screw locking the timing belt to the encoder shaft (located on the encoder assembly – rear of the cabin)
	<ul style="list-style-type: none"> Encoder shaft not connected to the encoder 	<ul style="list-style-type: none"> Tighten the grub screw locking the encoder to the encoder shaft (located on the encoder assembly – rear of the cabin)
<ul style="list-style-type: none"> Lift sinks below floor level over time 	<ul style="list-style-type: none"> Anti-creep not operating correctly 	<ul style="list-style-type: none"> Refer to wiring manual
<ul style="list-style-type: none"> Door will not open/unlock 	<ul style="list-style-type: none"> Lift not in door zone. Door zone switch not activated. 	<ul style="list-style-type: none"> Adjust door zone ramp position.
	<ul style="list-style-type: none"> No solenoid feed (SF) at door zone switch 	<ul style="list-style-type: none"> Refer to wiring manual
<ul style="list-style-type: none"> Structure creaking 	<ul style="list-style-type: none"> Lift not fixed back correctly / adequately 	<ul style="list-style-type: none"> Refer to builders work drawing, adjust / add structure fixings

20 Safety chain switch locations

Designation	Description	Location *
G1	Shutdown keyswitch	Main entrance landing station
G2	Pit stop and pit prop switches	Mounted on the base plate assembly in the pit
G3	Ultimate limit switch	Mounted on the outside of one sling upright
G4	Carriage stop switch	Mounted on the COP within the cabin
G5	Landing door beak contacts	Between the landing door and frame (at each landing)
G6	Solenoid lock switches	Mounted on each solenoid lock (at each landing)
G7	Solenoid feed monitor	G7 terminal can be found on carriage control PCB
G7A	Anti-creep relay	Located in the trailer connection box
G7B	Cabin floor safety edge	Mounted on the entrance side of the floor assembly
G7C	Cabin roof safety edge	Mounted on the entrance side of the roof assembly
G7D	Ceiling beak contacts	Mounted on the lock side of the ceiling
G8	Roof stop switch	Mounted on top of the guide side of the sling

* Refer to diagrams overleaf



21 Commissioning

Commissioning test

On completion of the installation the lift is ready to be tested. The test must be carried out according to the 'Midilift test and handover document'. The lift can only be commissioned once this has been correctly completed.

Uncontrolled movement test

The correct operation of the safety valve (DLV) must be verified as part of the commissioning process. To check the operation:

- a) Remove the two 19mm AF lock nuts from the solenoid stems
- b) Call the lift downwards.
- c) While the lift is descending, briefly lift the coil off of the main down valve (D) - the lift should stop immediately.
- d) Quickly replace the coil so that the lift descends again.
- e) Repeat steps (a) to (d) with the coil from the safety valve (DLV) - again the lift should stop immediately.


IF THE LIFT FAILS TO STOP IMMEDIATELY WHEN EITHER OF THE COILS ARE LIFTED, THE VALVE IS FAULTY AND CORRECTIVE ACTION MUST BE TAKEN BEFORE THE LIFT CAN BE HANDED OVER.

Note: If the lift is stationary for more than 4 seconds during a down journey an encoder fault 'FA' will occur. Do not leave the coils off the valve stems for more than a few seconds as they can overheat and become damaged.


Name plate (CE & UKCA mark)

After final commissioning of the lift, write the Lift Number and Year of Installation legibly on the name plate, using an indelible pen. Check that the model name corresponds to the Midilift SL+

The name plate is to be adhered in position, using the self-adhesive strip, in the recess located on the cabin operating panel, as shown below.



To be inserted by installer using an indelible pen.



Cleaning

Before handing the lift over to the customer, ensure the work place is tidy and the lift is clean.

The cabin interior and the inside/outside of the structure will need to be cleaned. To access the inside of the shaft for cleaning, the ceiling can be dropped and the roof centre board removed - by using a step ladder in the cabin, the inside of the structure can then be accessed. To run the lift with the ceiling open it will be necessary to use the pendant controller with a shorting link placed between G7C and G8 of the safety circuit - **ENSURE THIS LINK IS REMOVED BEFORE HANDOVER.**



DO NOT RUN THE LIFT WHILE AN ENGINEER IS USING THE CEILING ACCESS HATCH TO CLEAN THE LIFT SHAFT - THE ENGINEER MUST ALWAYS RETURN TO THE INSIDE OF THE CABIN BEFORE RAISING OR LOWERING THE LIFT.

Demonstration

When handing the lift over to the customer or the person responsible for the lift, the following must be demonstrated to him/her:

- i. Full operation of the lift controls.
- ii. The position and operation of all safety edges and surfaces.
- iii. The lift manual lowering procedure and the passenger release procedure.
- iv. Ensure the customer is aware of who to contact in case of a break down.

Before leaving the site you must ensure the customer has run through a complete operation of the lift and is completely satisfied with the product.

22 Document History

Issue	Name	Changes	Date
1	R Christopher	First issue	04/09/13
2	T Lloyd	Tolerance for ultimate limit switch position was +0/-25mm. (Pg 61)	18/01/19
3	G Howard	Max packer height noted along with required floor fixing torque (Pg. 11 & 52 respectively)	19/03/19
4	R. Lark	Notes relating to ram guide joiners and reference to builders' work drawing added (Pg. 33)	11/12/19
5	R Christopher	Section 8 Door Installation – information updated to show 30mm intumescent seals on 60 minute fire doors	06/02/2020
6	R Christopher	<ul style="list-style-type: none"> 1.2 – lifting eyebolt & motor support plate added to tool list 5.1 – torque value and visual check added for all M12 guide clips 5.3 – updated to show bottom reset ramp 6.1 – images updated to show latest upper hanging bracket for work platform 15 – removal of OPS assembly (discontinued Aug 2016) 	07/04/2021
7	P. Jeffery	Section 8 - Fire door information updated to show 30mm intumescent seals on both 30-minute and 60-minute fire doors	27/06/2022
8	R Christopher P Jeffery	<ul style="list-style-type: none"> 1.2 - image for upper hanging brackets updated 6.1 – Instruction to fit upper hanging brackets & fixings added 11.3 – Fixing information for upper hitch brackets on Work Platform corrected (was M16 x 90 in error). 8 - Image and note for 3mm strip spacer added to fire door frame if required. 	25/07/2022
9	P. Jeffery	Name plate added to Section 21- Commissioning. New requirements for displaying the UKCA mark.	03/01/2023