



An independent family business since 1867

Piccolo Wall Mounted


Vertical platform lift with hydraulic drive & cabin with automatic sliding doors (shaft by others)

Stannah

Specifications:

Rated Load: 400kg, 5 Person
 Rated Speed: 0.15m/s
 Maximum Travel: 12m
 Maximum number of stops: 5
 Pit Depth: 150mm
 Minimum Headroom: 2500mm
 Cabin internal dimensions: CW x CD x 2000 high
 Doors: Automatic 2 panel side opening, DO x 2000 high
 Controls: Latched call controls as standard.

Cabin Size CW x CD (Note 3)	Door Opening DO	Door Config	Min Plumb Shaft Size (+50/-0)		Structural Opening SO	X
			SW	SD		
1100 x 1400	900	Single	1550	1750	1160	390
		Through	1550	1960		
950 x 1400	800	Single	1400	1750	1060	340
		Through	1400	1960		
950 x 1250	800	Single	1400	1600	1060	340
		Through	1400	1810		



30mm gaps to be 'made good' by builder once door frames are in position

Notes:

- All dimensions in mm unless stated.
- Minimum floor to floor dimensions:
 - between consecutive floors on same side = 2400mm minimum
 - between consecutive floors on opposing sides = 180mm minimum
 - between terminal floors = 1000mm minimum
- 1100 x 1400 cabins are Part M (England & Wales) and section 4.2 of the Technical Handbook (Scotland) compliant, 950 x 1400 cabins are Part M (England & Wales) compliant.
- Range of cabin finishes available, please contact us for further information.

Electrical Requirements:

- Provide a dedicated single phase supply protected by a 16amp type D MCB. The lift supply is to terminate in a lockable isolator at a position shown on builders work diagram.
- Provide a 13amp electrical outlet socket adjacent to the lift installations at all levels. The supply to these sockets is not to be derived from the lift supply detailed in Note 5 above.
- Ensure that lighting at all landing levels is not less than 50lux.

Fixings:

- Provisions for fixings and loads imposed by the lift are required on the guide side wall and entrance wall(s) - refer to relevant 'Loads & Fixings' information sheet or site specific Builders Work Drawing for details.
- It shall be the customer's responsibility to ensure suitability of the building structure for the applied loads, both in terms of strength & also suitability of the fixings proposed. If any doubts exist, it is advised that a structural engineer is consulted.

Drive Unit:

- The drive unit is housed in a separate enclosure, which should be located within 5m of the base of the lift (guide side).

Scaffolding:

- Scaffolding must be provided and erected in the lift shaft - refer to site specific Builders Work Drawing for details.

Structural Openings:

- Lowest landing: front wall nib (X) to be left down to permit installation of lift equipment, i.e. structural opening = X + SO

All other landings: structural opening = SO (see 'Plan View')

Typical 2 Floor Arrangement

Waiver

The data sheet is for guidance only & must not be used for proper working drawings. Please contact us for particular details before proceeding. Owing to our policy of continual improvement, we reserve the right to alter specifications & dimensions without prior notice.

Stannah Lifts Ltd.
 Anton Mill, Andover,
 Hampshire, SP10 2NX
 Tel: 01264 339090
 www.stannahlifts.co.uk

Information sheet
P801
 30/01/2018